

	LEGEND		
	EXISTING	PROPOSED	
WATER LINE		uwuw	
FIRE HYDRANT	\$	₩	
FDC		₩	
PIV		•	
WATER VALVE	₩2	\otimes	
GAS LINE	G	UG	
GAS METER	GM		
GAS VALVE	Ø		
OVERHEAD WIRES			
UTILITY POLE	-0-		
UNDERGROUND ELECTRIC	Ε	UE	
ELECTRIC METER	[EM]		
ELECTRIC STRUCTURE	E		
TRANSFORMER			
LIGHTING FIXTURES	0-8-0 0-0		
UNDERGROUND TELEPHONE	т	uT	
SANITARY SEWER LINE	s	US	
SANITARY MANHOLE		•	
SANITARY CLEANOUT	oco	•	
STORM PIPE			
CATCH BASIN			
TRENCH DRAIN			
STORM MANHOLE	0	•	
YARD DRAIN	0		
STORM CLEANOUT	oco	°co	
4" PVC IRRIGATION SLEEVE			

UTILITY GENERAL NOTES

- THE CONTRACTOR IS RESPONSIBLE TO BECOME THOROUGHLY FAMILIAR WITH THE ENGINEERING, DRAINAGE, AND UTILITY STANDARDS OF THE LOCAL MUNICIPALITY AND COUNTY THAT THE PROJECT IS LOCATED IN. ALL LOCAL MUNICIPALITY AND COUNTY STANDARDS WILL TAKE PRECEDENCE OVER THE DETAILS, SPECIFICATIONS, AND NOTES PROVIDED ON THESE DRAWINGS, UNLESS SPECIFICALLY ADDRESSED OTHERWISE BY LANGAN DURING THE PROJECT UPON REQUEST FROM THE
- THE CONTRACTOR SHALL NOTIFY OHIO UTILITIES PROTECTION SERVICES, AND ANY OTHER UTILITY COMPANIES NOT REPRESENTED BY OHIO UTILITIES PROTECTION SERVICES, 48 HOURS PRIOR TO EXCAVATING INITIATION. NOTIFY OHIO UTILITIES PROTECTION SERVICES AT 1-800-362-2764. CONTRACTOR MUST CONTACT UTILITY COMPANIES FOR EXACT LOCATIONS OF UTILITIES 2 WORKING DAYS BEFORE DIGGING.
- 3. CONTRACTOR SHALL VERIFY LOCATION AND ELEVATION OF ALL PROPOSED CONNECTIONS TO EXISTING FACILITIES PRIOR TO COMMENCING WORK. IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY LANGAN OF ANY DISCREPANCIES.
- 4. TRENCH DEPTH REQUIREMENTS MEASURED FROM FINISHED GRADE SHALL MEET THE FOLLOWING: STORM SEWER: DEPTHS, ELEVATIONS, AND GRADES AS INDICATED ON DRAWINGS. SANITARY SEWER: DEPTHS, ELEVATIONS AND GRADES AS INDICATED ON DRAWINGS. . WATER MAINS: 72 INCHES TO TOP OF PIPE BARREL OR 6 INCHES BELOW THE FROST LINE OR ESTABLISHED BY THE
- LOCAL BUILDING OFFICIAL OR WATER COMPANY, WHICHEVER IS DEEPER. . GAS MAINS AND SERVICE: 30 INCHES MINIMUM TO TOP OF PIPE, OR AS REQUIRED BY THE LOCAL UTILITY COMPANY, WHICHEVER IS DEEPER. • ELECTRICAL CONDUITS: 24 INCHES MINIMUM TO TOP OF CONDUIT OR AS REQUIRED BY NEC 300-5 / NEC 710-36 CODES, OR THE LOCAL UTILITY COMPANY REQUIREMENTS, WHICHEVER IS DEEPER.
- TELEPHONE / TV CONDUITS: 18 INCHES MINIMUM TO TOP OF CONDUIT OR AS REQUIRED BY THE LOCAL UTILITY COMPANY, WHICHEVER IS DEEPER. 5. UTILITY TESTING INCLUDING (BUT NOT LIMITED TO) WATER PRESSURE TESTING, WATER SYSTEM FLUSHING, BACTERIOLOGICAL TESTING, VIDEO CAMERA TESTING, MANDREL TESTING, OR ANY OTHER TESTING REQUIRED BY LOCAL, COUNTY, OR STATE AGENCIES PRIOR TO FINAL ACCEPTANCE OF THE PROJECT AND CERTIFICATE OF OCCUPANCIES BEING ISSUED SHALL BE
- COORDINATED AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER. THE ENGINEER OF RECORD SHALL BE GIVEN 48 HOURS NOTICE PRIOR TO ALL TESTING. THE CONTRACTOR IS SOLELY RESPONSIBLE TO CONTACT AND COORDINATE THE LOCAL AND COUNTY OFFICIALS THAT ARE REQUIRED TO BE PRESENT AT ALL INSPECTIONS. LOCAL FIRE INSPECTORS SHALL BE INVITED TO INSPECT ALL FIRE SERVICE LINES PRIOR TO BACKFILLING OF TRENCHES. 6. THE LOCATIONS (VERTICAL AND HORIZONTAL) OF ALL EXISTING UTILITIES SHOWN ON THESE DRAWINGS ARE APPROXIMATE.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE EXACT LOCATION OF THE UTILITIES PRIOR TO CONSTRUCTION. ANY UTILITIES (WHETHER THEY ARE SHOWN OR NOT SHOWN ON THE DRAWINGS) DAMAGED BY THE CONTRACTOR SHALL BE
- . WHERE CONFLICTS ARISE BETWEEN EXISTING OR PROPOSED WATER LINES AND OTHER UTILITIES, STORMWATER CONVEYANCE SYSTEMS OR STRUCTURES, THE WATER LINES SHALL BE ADJUSTED BENEATH OR AROUND THE CONFLICT AS NECESSARY IN ACCORDANCE WITH ACCEPTED CONSTRUCTION PRACTICES.

8. ALL WATERLINES AND APPURTENANCES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE STANDARDS AND

SPECIFICATIONS ESTABLISHED BY THE CLEVELAND WATER DEPARTMENT AND THE OHIO EPA. APPROVED BY THE OHIO EPA AND CLEVELAND WATER DEPARTMENT.

10. ANY EXISTING HYDRANTS, VALVES, VALVE BOXES, METER PITS, SERVICE LINES, CURB BOXES OR WATERMAINS THAT ARE DAMAGED OR MUST BE ADJUSTED AND/OR MOVED, MUST BE REPAIRED, ADJUSTED, MOVED AND/OR REPLACED AT THE

11. PVC POTABLE WATER MAINS SHALL BE SOLID BLUE IN COLOR. DUCTILE IRON WATER MAINS SHALL BE PAINTED WITH BLUE

- BANDS. CONTRACTORS SHALL INSTALL ALL NEW OR ALTERED WATER PIPES IN ACCORDANCE WITH APPLICABLE AWWA STANDARDS AND / OR ACCORDANCE WITH MANUFACTURER'S RECOMMENDED PROCEDURES. 12. ALL WATER MAINS SHALL BE HYDROSTATICALLY TESTED AND DISINFECTED IN ACCORDANCE WITH AWWA STANDARDS, LATEST REVISIONS. HYDROSTATIC TESTING FOR PVC MAINS SHALL BE 150 PSI FOR MINIMUM OF 2 HOURS AND MEET AWWA
- STANDARD C-605. DUCTILE IRON MAINS SHALL BE TESTED AT 150 PSI FOR 2 HOURS AND MEET AWWA STANDARD C-600. ALL NEW MAINS SHALL BE DISINFECTED PER AWWA STANDARD C-651. BACTERIOLOGICAL TESTS FOR 2 CONSECUTIVE DAYS SHALL BE APPROVED PRIOR TO PLACING SYSTEM INTO SERVICE. CONTRACTOR SHALL PROVIDE THE OWNER AND ENGINEER OF RECORD WITH AWWA C906 AND NSF-61 CERTIFICATIONS. 13. ALL UTILITIES SHALL HAVE AN "EARLY WARNING" PROTECTION TAPE INSTALLED CONTINUOUSLY ALONG THE ENTIRE LENGTH. THE PROTECTION TAPE SHALL BE INSTALLED DURING THE BACKFILLING 6 TO 12 INCHES BELOW FINISHED GRADE DIRECTLY
- OVER THE PIPE AND BE CONTINUOUSLY MARKED WITH "CAUTION (TYPE OF UTILITY) BURIED BELOW". THE TAPE SHALL HAVE AN EMBEDDED METALLIC DETECTABLE STRIP AND FOLLOW ANSI STANDARD Z535.1 SPECIFICATIONS FOR SAFETY COLORS, PROTECTION TAPE SHALL BE TERRA-TAPE OR APPROVED EQUAL. 14. ALL GRAVITY SANITARY SEWER PIPE SHALL BE PVC, ASTM D-3034, SDR35, WITH RUBBER GASKET JOINTS IN ACCORDANCE
- 15. ROOF DRAINS, FOUNDATION DRAINS, AND OTHER CLEAN WATER CONNECTIONS TO THE SANITARY SEWER ARE PROHIBITED.
- 16. PROVIDE CLEANOUTS AT EACH 45' AND 90' BEND, REFER TO DETAIL SHEET FOR TYPICAL CLEANOUT DETAIL.
- 17. ALL SEWER LINE CONSTRUCTION MUST BE INSPECTED BY THE LOCAL AUTHORITY OR AUTHORIZED REPRESENTATIVE. 18. AT THE POINT WHERE THE PROPOSED SANITARY SEWER CONSTRUCTION MEETS A LIVE OR EXISTING SEWER, THE NEW SANITARY SEWER SHALL BE SECURELY PLUGGED UNTIL THE ENTIRE NEW SANITARY SEWER CONSTRUCTION IS COMPLETED AND READY FOR FINAL INSPECTION.
- 19. SANITARY SEWER PIPE SHALL BE SUBJECT TO A LEAKAGE AND DEFLECTION TEST. THE LEAKAGE EXFILTRATION/INFILTRATION TEST SHALL BE A HYDROSTATIC OR AIR TEST. THE HYDROSTATIC LEAKAGE TEST SHALL NO EXCEED 100 GALLONS PER INCH OF PIPE DIAMETER PER MILE PER DAY FOR ANY SECTION OF THE SYSTEM. THE LOW AIR PRESSURE TESTING SHALL FOLLOW THE PROCEDURE OUTLINED IN ASTM F-1417 FOR PLASTIC PIPE. SANITARY SEWER PIPE SHALL NOT EXCEED A MAXIMUM DEFLECTION OF 5 PERCENT AFTER THE FINAL BACKFILL HAS BEEN IN PLACE NO LESS THAN 30 DAYS TO PERMIT STABILIZATION OF THE SOIL-PIPE SYSTEM. THE RIGID BALL OR MANDREL USED FOR THE DEFLECTION TEST SHALL HAVE A DIAMETER NOT LESS THAN 95 PERCENT OF THE BASE INSIDE DIAMETER OR AVERAGE INSIDE DIAMETER OF THE PIPE DEPENDING ON WHICH IS SPECIFIED IN THE ASTM SPECIFICATION, INCLUDING THE APPENDIX, TO WHICH THE PIPE IS MANUFACTURED. THE TEST SHALL BE PERFORMED WITHOUT MECHANICAL PULLING DEVICES. THE LEAKAGE AND DEFLECTION TEST SHALL BE CONDUCTED UNDER THE SUPERVISION OF A PROFESSIONAL ENGINEER. ANY LINES WHICH FAIL THE DEFLECTION OR LEAKAGE TEST MUST BE REPAIRED AND RETESTED UNTIL THEY MEET THE REQUIREMENTS WHICH HAVE BEEN SET FORTH.
- 9. BACKFLOW DEVICE REQUIRED ON ALL SERVICE CONNECTIONS. THE BACKFLOW PREVENTER SHALL BE TESTABLE AND LISTED 20. ANY UTILITY CONFLICTS WITH 18 INCHES OR LESS VERTICAL SEPARATION BETWEEN OUTSIDE OF PIPE AND OUTSIDE OF PIPE SHALL BE CONCRETE ENCASED.

- 21. ONCE EXISTING UTILITIES TO REMAIN ARE LOCATED, ANY POTENTIAL CONFLICTS WITH OTHER UTILITIES, RELOCATED UTILITY POLES, ETC, SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER IMMEDIATELY. 22. ALL TRENCHING, PIPE LAYING, AND BACKFILLING SHALL BE IN ACCORDANCE WITH FEDERAL OSHA REGULATIONS AND ANY
- 23. THE CONTRACTOR SHALL BE RESPONSIBLE FOR TRENCHING, BEDDING AND BACKFILLING ACTIVITIES, INSTALLATION OF ALL CONDUIT, PLACEMENT OF PULL WIRES WITHIN THE SITE AND GROUNDING.
- 24. ALL STORM DRAINAGE PIPES ARE TO BE AS SPECIFIED ON THE PLANS: HIGH-DENSITY POLYETHYLENE PIPE (HDPE): AASHTO M294 TYPE S FOR PIPE AND FITTINGS. MATERIAL SHALL MEET ASTM 01298 TYPE III, CATEGORY 4, GRADE P33, CLASS C, OR ASTM D3350 CELL CLASSIFICATION 324420C. PIPE SHALL BE SURE—LOK 10.8 PIPE MANUFACTURED BY HANCOR, INC. WITH WATERTIGHT JOINTS ACCORDING TO THE REQUIREMENTS OF ASTM D3212, OR APPROVED EQUAL. INSTALLATION SHALL BE IN ACCORDANCE WITH ASTM 02321.
- 25. ALL DRAINAGE STRUCTURES AND STORM SEWER PIPES SHALL MEET HEAVY DUTY TRAFFIC (HS20) LOADING AND BE
- 26. ALL CLEANOUTS SHALL BE FLUSH WITH THE FINAL SURFACE GRADE. 27. COORDINATE STORM, SANITARY, WATER, ELECTRIC, COMMUNICATION AND GAS UTILITIES AND APPURTENANCES WITHIN 5
- FEET OF BUILDING WITH ARCHITECTURAL PLANS. 28. CONTRACTOR TO COORDINATE INSTALLATION OF UTILITIES WITH LOCAL UTILITY COMPANIES.
- 29. SEE ARCHITECTURAL PLANS FOR BUILDING UTILITY REQUIREMENTS.
- 30. COORDINATE THE SCOPE AND RESPONSIBILITY OF ALL WORK WITH THE LOCAL UTILITY PRIOR TO BIDDING PROJECT, OBTAIN INSTALLATION REQUIREMENTS. 31. CONTRACTOR TO VERIFY EXISTING STORM SEWER AND SANITARY LATERAL ARE IN GOOD CONDITION AND FREE FLOWING.
- 32. CONTRACTOR TO COORDINATE WITH IRRIGATION CONTRACTOR TO DESIGN IRRIGATION SYSTEM. CONTRACTOR TO PROVIDE 4" IRRIGATION SLEEVES AS SHOWN FOR IRRIGATION CONTRACTORS USE. 33. CONTRACTOR TO INSTALL HANDHOLES & PULLBOXES AS DETERMINED APPROPRIATE BY CONTRACTOR AND UTILITY

PROPOSED CORE AND SHELL BUILDING:

Convergent East

2 Equity Way Westlake, OH 44145

JOB NUMBER: **180393.00**

No. Date

01/04/2019


DRAWING RELEASE:

Permit/Bid Set

SHEET TITLE:

SHEET NUMBER:

UTILITY PLAN



GENERAL LANDSCAPE PLANTING NOTES

- 1. NAMES OF PLANTS AS DESCRIBED ON THIS PLAN CONFORM TO THOSE GIVEN IN "STANDARDIZED PLANT NAMES OF PLANT VARIETIES NOT INCLUDED THEREIN CONFORM TO NAMES GENERALLY ACCEPTED IN NURSERY TRADE.
- 2. ALL EXPOSED GROUND SURFACES THAT ARE NOT PAVED WITHIN THE CONTRACT LIMIT LINE, AND THAT ARE NOT COVERED BY LANDSCAPE PLANTING OR SEEDING AS SPECIFIED, SHALL BE COVERED BY A NATURAL MULCH THAT WILL PREVENT SOIL EROSION AND THE EMANATION OF DUST ..
- 3. NO PLANT SHALL BE PUT INTO THE GROUND BEFORE ROUGH GRADING HAS BEEN COMPLETED AND APPROVED BY THE PROJECT LANDSCAPE ARCHITECT OR PROJECT ENGINEER.
- 4. STANDARDS FOR TYPE, SPREAD, HEIGHT, ROOT BALL AND QUALITY OF NEW PLANT MATERIAL SHALL BE IN ACCORDANCE WITH GUIDELINES AS SET FORTH IN THE "AMERICAN STANDARD FOR NURSERY STOCK", PUBLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMEN. PLANT MATERIAL SHALL HAVE NORMAL HABIT OF GROWTH AND BE HEALTHY, VIGOROUS, AND FREE FROM DISEASES AND INSECT INFESTATION.
- 5. NEW PLANT MATERIAL SHALL BE NURSERY GROWN UNLESS SPECIFIED OTHERWISE. ALL PLANTS SHALL BE SET PLUMB AND SHALL BEAR THE SAME RELATIONSHIP TO FINISHED GRADE AS THE PLANT'S ORIGINAL GRADE BEFORE DIGGING. PLANT MATERIAL OF THE SAME SPECIES AND SPECIFIED AS THE SAME SIZE SHOULD BE SIMILAR IN SHAPE, COLOR AND HABIT. THE LANDSCAPE ARCHITECT HAS THE RIGHT TO REJECT PLANT MATERIAL THAT DOES NOT CONFORM TO THE TYPICAL OR SPECIFIED HABIT OF THAT SPECIES.
- 6. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING UNDERGROUND UTILITY AND SEWER LINES PRIOR TO THE START OF EXCAVATION ACTIVITIES. NOTIFY THE PROJECT ENGINEER AND OWNER IMMEDIATELY OF ANY CONFLICTS WITH PROPOSED PLANTING LOCATIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE.
- 7. THE CONTRACTOR SHALL NOT MAKE SUBSTITUTIONS. IF THE SPECIFIED LANDSCAPE MATERIAL IS NOT OBTAINABLE, THE CONTRACTOR SHALL SUBMIT PROOF OF NON-AVAILABILITY TO THE LANDSCAPE ARCHITECT AND OWNER, TOGETHER WITH A WRITTEN PROPOSAL FOR USE OF AN EQUIVALENT MATERIAL.
- 8. LANDSCAPE CONTRACTOR TO STAKE OUT PLANTING LOCATIONS, FOR REVIEW AND APPROVAL BY THE LANDSCAPE ARCHITECT AND/OR OWNER BEFORE PLANTING WORK BEGINS. THE LANDSCAPE ARCHITECT AND/OR OWNER SHALL DIRECT THE CONTRACTOR IN THE FINAL PLACEMENT OF ALL PLANT MATERIAL AND LOCATION OF PLANTING BEDS TO ENSURE COMPLIANCE WITH DESIGN INTENT UNLESS OTHERWISE INSTRUCTED.
- 9. THE LANDSCAPE ARCHITECT MAY REVIEW PLANT MATERIALS AT THE SITE, BEFORE PLANTING, FOR COMPLIANCE WITH REQUIREMENTS FOR GENUS, SPECIES, VARIETY, SIZE, AND QUALITY. THE LANDSCAPE ARCHITECT RETAINS THE RIGHT TO FURTHER REVIEW PLANT MATERIALS FOR SIZE AND CONDITION OF BALLS AND ROOT SYSTEM, INSECTS, INJURIES, AND LATENT DEFECTS, AND TO REJECT UNSATISFACTORY OR DEFECTIVE MATERIAL AT ANY TIME DURING PROGRESS OF WORK. THE CONTRACTOR SHALL REMOVE REJECTED PLANT MATERIALS IMMEDIATELY FROM PROJECT SITE AS DIRECTED BY THE LANDSCAPE ARCHITECT
- 10. THE PROJECT LANDSCAPE ARCHITECT SHALL CERTIFY THAT THE LANDSCAPE PLAN HAS BEEN INSTALLED PER THE CONTRACT DOCUMENTS ONCE THE PROJECT HAS REACHED SUBSTANTIAL COMPLETION.
- 11. DELIVERY, STORAGE, AND HANDLING A. PACKAGED MATERIALS: PACKAGED MATERIALS SHALL BE DELIVERED IN CONTAINERS SHOWING WEIGHT, ANALYSIS, AND NAME OF MANUFACTURER. MATERIALS SHALL BE PROTECTED FROM DETERIORATION
- DURING DELIVERY, AND WHILE STORED AT SITE. B. TREES AND SHRUBS: THE CONTRACTOR SHALL PROVIDE TREES AND SHRUBS DUG FOR THE GROWING SEASON FOR WHICH THEY WILL BE PLANTED. DO NOT PRUNE PRIOR TO DELIVERY UNLESS OTHERWISE DIRECTED BY THE LANDSCAPE ARCHITECT. DO NOT BEND OR BIND-TIE TREES OR SHRUBS IN SUCH A MANNER AS TO DAMAGE BARK, BREAK BRANCHES, OR DESTROY NATURAL SHAPE. PROVIDE PROTECTIVE

COVERING DURING TRANSIT. DO NOT DROP BALLED AND BURLAPPED STOCK DURING DELIVERY OR

- C. ALL PLANTS SHALL BE BALLED AND BURLAPPED OR CONTAINER GROWN AS SPECIFIED. NO CONTAINER GROWN STOCK WILL BE ACCEPTED IF IT IS ROOT BOUND. ALL ROOTBALL WRAPPING AND BINDING MATERIAL MADE OF SYNTHETICS OR PLASTICS SHALL BE REMOVED FROM THE TOP OF THE BALL AT THE TIME OF PLANTING. IF THE PLANT IS SHIPPED WITH A WIRE BASKET AROUND THE ROOT BALL, THE WIRE BASKET SHALL BE CUT AND FOLDED DOWN 8 INCHES INTO THE PLANTING HOLE. WITH CONTAINER GROWN STOCK, THE CONTAINER SHALL BE REMOVED AND THE ROOT BALL SHALL BE CUT THROUGH THE
- SURFACE IN TWO LOCATIONS. THE CONTRACTOR SHALL HAVE TREES AND SHRUBS DELIVERED TO SITE AFTER PREPARATIONS FOR PLANTING HAVE BEEN COMPLETED AND PLANT IMMEDIATELY. IF PLANTING IS DELAYED MORE THAN 6 HOURS AFTER DELIVERY, THE CONTRACTOR SHALL SET TREES AND SHRUBS IN SHADE, PROTECT FROM WEATHER AND MECHANICAL DAMAGE AND KEEP ROOTS MOIST BY COVERING WITH MULCH, BURLAP OR OTHER ACCEPTABLE MEANS OF RETAINING MOISTURE
- 12. ALL LANDSCAPED AREAS TO BE CLEARED OF ROCKS, STUMPS, TRASH AND OTHER UNSIGHTLY DEBRIS. ALL FINE GRADED AREAS SHOULD BE HAND RAKED SMOOTH ELIMINATING ANY CLUMPS AND AND UNEVEN SURFACES PRIOR TO PLANTING OR MULCHING.
- 13. ALL PLANT MATERIAL SHALL BE INSTALLED AS PER DETAILS, NOTES AND CONTRACT SPECIFICATIONS. THE LANDSCAPE ARCHITECT MAY REVIEW INSTALLATION AND MAINTENANCE PROCEDURES.
- 14. NEW PLANT MATERIAL SHALL BE GUARANTEED TO BE ALIVE AND IN VIGOROUS GROWING CONDITION FOR A PERIOD OF TWO YEARS FOLLOWING ACCEPTANCE BY THE OWNER. PLANT MATERIAL FOUND TO BE UNHEALTHY, DYING OR DEAD DURING THIS PERIOD, SHALL BE REMOVED AND REPLACED IN KIND BY THE CONTRACTOR AT NO EXPENSE TO THE OWNER.
- 15. THE CONTRACTOR SHALL KEEP AREA CLEAN DURING DELIVERY AND INSTALLATION OF PLANT MATERIALS. REMOVE AND DISPOSE OF OFF-SITE ANY ACCUMULATED DEBRIS OR UNUSED MATERIALS. REPAIR DAMAGE TO ADJACENT AREAS CAUSED BY LANDSCAPE INSTALLATION OPERATIONS.
- 16. ALL PLANTS SHALL BE WATERED THOROUGHLY TWICE DURING THE FIRST 24-HOUR PERIOD AFTER PLANTING. ALL PLANTS SHALL THEN BE WATERED WEEKLY OR AS REQUIRED BY SITE AND WEATHER CONDITIONS TO MAINTAIN VIGOROUS AND HEALTHY PLANT GROWTH.
- 17. THE BACKFILL MIXTURE AND SOIL MIXES TO BE INSTALLED PER THE SPECIFICATIONS.
- 18. AFTER PLANT IS PLACED IN TREE PIT LOCATION. ALL TWINE HOLDING ROOT BALL TOGETHER SHOULD BE COMPLETELY REMOVED AND THE BURLAP SHOULD BE PULLED DOWN SO 1/3 OF THE ROOT BALL IS EXPOSED. SYNTHETIC BURLAP SHOULD BE COMPLETELY REMOVED AFTER INSTALLATIÓN.
- 19. MULCH SHOULD NOT BE PILED UP AROUND THE TRUNK OF ANY PLANT MATERIAL, NO MULCH OR TOPSOIL SHOULD BE TOUCHING THE BASE OF THE TRUNK ABOVE THE ROOT COLLAR.
- 20. ALL FENCE INSTALLATION SHALL BE COMPLETED PRIOR TO COMMENCEMENT OF ANY LANDSCAPE PLANTING, LAWN AND GRASSES, OR IRRIGATION WORK.
- 21. FOR ANY DISCREPANCIES BETWEEN THE PLANT SCHEDULE AND PLANTING PLAN THE GRAPHIC QUANTITY
- 22. PLANT MATERIALS SHALL NOT BE PLANTED UNTIL THE FINISHED GRADING HAS BEEN COMPLETED. 23. ALL PLANT INSTALLATIONS SHALL BE COMPLETED EITHER BETWEEN APRIL 1 - JUNE 15 OR AUGUST 15 -NOVEMBER 1, UNLESS OTHERWISE DIRECTED BY THE PROJECT LANDSCAPE ARCHITECT. SEE LAWN SEEDING

CLEAN SOIL FILL IN LANDSCAPE AREAS: NAMES", 1942 EDITION, PREPARED BY THE AMERICAN JOINT COMMITTEE ON HORTICULTURAL NOMENCLATURE. LANDSCAPE FILL MATERIAL SHALL HAVE THE PHYSICAL PROPERTIES OF A SANDY LOAM WITH AN ORGANIC CONTENT OF LESS THAN 2% AND A PH BETWEEN 5 - 7.

> CONTRACTOR TO PROVIDE SIX INCHES (6") MINIMUM DEPTH PLANTING SOIL LAYER IN LAWN AREAS, TWELVE INCHES (12") MINIMUM DEPTH PLANTING SOIL LAYER IN GROUNDCOVER AND PERENNIAL AREAS, EIGHTEEN INCHES (18") MINIMUM DEPTH PLANTING SOIL LAYER IN SHRUB AREAS, AND THIRTY-SIX INCHES (36") MINIMUM DEPTH PLANTING SOIL LAYER IN TREE PLANTING AREAS. PLANTING SOIL SHOULD BE SPREAD OVER A PREPARED SURFACE IN SIX INCH (6") LIFTS UNTIL FULL DEPTHS ARE ACHIEVED AS DESCRIBED ABOVE. PLANTING SOIL PRESENT AT THE SITE, IF ANY, MAY BE USED TO SUPPLEMENT TOTAL AMOUNT REQUIRED. CONTRACTOR TO FURNISH AN ANALYSIS OF ON-SITE PLANTING SOIL UTILIZED IN ALL PLANTING AREAS. ADJUST pH AND NUTRIENT LEVELS AS REQUIRED TO ENSURE AN ACCEPTABLE GROWING MEDIUM. LOWER PH USING ELEMENTAL SULFUR ONLY. PEAT MOSS OR COPPER SULFATE MAY NOT BE USED. GROUND LIMESTONE AS A SOIL AMENDMENT MATERIAL WILL ONLY BE USED PENDING RESULTS OF SOIL ANALYSIS. PROVIDE WITH MINIMUM 88% CALCIUM AND MAGNESIUM CARBONATES AND SHALL HAVE TOTAL 100% PASSING THE 10 MESH SIEVE, MINIMUM 90% PASSING 20 MESH SIEVE, AND MINIMUM 60% PASSING 100 MESH SIEVE. ALL DEBRIS EXPOSED FROM EXCAVATION AND

SOIL MODIFICATIONS (PENDING RESULTS OF SOIL ANALYSIS): THOROUGHLY TILL ORGANIC MATTER (LEAF COMPOST) INTO THE TOP 6 TO 12 IN. OF MOST PLANTING SOILS TO IMPROVE THE SOIL'S ABILITY TO RETAIN WATER AND NUTRIENTS. ALL PRODUCTS SHOULD BE COMPOSTED TO A DARK COLOR AND BE FREE OF PIECES WITH IDENTIFIABLE LEAF OR WOOD STRUCTURE. AVOID MATERIAL WITH A PH HIGHER THAN 7.0. PEAT MOSS MAY NOT BE USED AS ORGANIC MATTER AMENDMENT.

MODIFY HEAVY CLAY OR SILT (MORE THAN 40% CLAY OR SILT) BY ADDING COMPOSTED PINE BARK (UP TO 30% BY VOLUME) AND/OR GYPSUM. COARSE SAND MAY BE USED IF ENOUGH IS ADDED TO BRING THE SAND CONTENT TO MORE THAN 60% OF THE TOTAL MIX. IMPROVE DRAINAGE IN HEAVY SOILS BY PLANTING ON RAISED MOUNDS OR BEDS AND INCLUDING SUBSURFACE DRAINAGE LINES.

MODIFY EXTREMELY SANDY SOILS (MORE THAN 85% SAND) BY ADDING ORGANIC MATTER AND/OR DRY, SHREDDED CLAY

LANDSCAPE MAINTENANCE NOTES

1. MAINTENANCE OPERATIONS BEFORE APPROVAL:

KEEP THE PLANTS IN A HEALTHY CONDITION.

LOAM UP TO 30% OF THE TOTAL MIX.

CULTIVATION SHALL BE DISPOSED OF AT THE CONTRACTOR'S EXPENSE.

- A. PLANT CARE SHALL BEGIN IMMEDIATELY AFTER EACH PLANT IS SATISFACTORILY INSTALLED AND SHALL CONTINUE THROUGHOUT THE LIFE OF THE CONTRACT UNTIL FINAL ACCEPTANCE OF THE PROJECT
- B. CARE SHALL INCLUDE, BUT NOT BE LIMITED TO, REPLACING MULCH THAT HAS BEEN DISPLACED BY EROSION OR OTHER MEANS, REPAIRING AND RESHAPING WATER RINGS OR SAUCERS, MAINTAINING STAKES AND GUYS AS ORIGINALLY INSTALLED, WATERING WHEN NEEDED OR DIRECTED, AND PERFORMING ANY OTHER WORK REQUIRED TO
- C. CONTRACTOR SHALL REMOVE AND REPLACE ALL DEAD, DEFECTIVE AND/OR REJECTED PLANTS AS REQUIRED BEFORE FINAL ACCEPTANCE.

2. MAINTENANCE DURING CONSTRUCTION:

- A. MAINTENANCE SHALL BEGIN IMMEDIATELY AFTER PLANTING. PLANTS SHALL BE WATERED, MULCHED, WEEDED, PRUNED, SPRAYED, FERTILIZED, CULTIVATED, AND OTHERWISE MAINTAINED AND PROTECTED UNTIL PROVISIONAL ACCEPTANCE. SETTLED PLANTS SHALL BE RESET TO PROPER GRADE AND POSITION, PLANTING SAUCER RESTORED AND DEAD MATERIAL REMOVED. STAKES AND WIRES SHALL BE TIGHTENED AND REPAIRED. DEFECTIVE WORK SHALL BE CORRECTED AS SOON AS POSSIBLE AFTER IT BECOMES APPARENT AND WEATHER AND SEASON PERMIT
- B. IF A SUBSTANTIAL NUMBER OF PLANTS ARE SICKLY OR DEAD AT THE TIME OF INSPECTION, ACCEPTANCE SHALL NOT BE GRANTED AND THE CONTRACTOR'S RESPONSIBILITY FOR MAINTENANCE OF ALL PLANTS SHALL BE EXTENDED FROM THE TIME REPLACEMENTS ARE MADE OR EXISTING PLANTS ARE DEEMED ACCEPTABLE BY THE LANDSCAPE ARCHITECT.
- C. ALL REPLACEMENTS SHALL BE PLANTS OF THE SAME KIND AND SIZE SPECIFIED ON THE PLANT LIST OR THAT WHICH WAS TO REMAIN OR BE RELOCATED. THEY SHALL BE FURNISHED AND PLANTED AS SPECIFIED. THE COST SHALL BE BORNE BY THE CONTRACTOR. REPLACEMENTS RESULTING FROM REMOVAL, LOSS, OR DAMAGE DUE TO OCCUPANCY OF THE PROJECT IN ANY PART, VANDALISM, PHYSICAL DAMAGE BY ANIMALS, VEHICLES, ETC., AND LOSSES DUE TO CURTAILMENT OF WATER BY LOCAL AUTHORITIES SHALL BE APPROVED AND PAID FOR BY THE
- D. PLANTS SHALL BE GUARANTEED FOR A PERIOD OF TWO YEARS AFTER INSPECTION AND PROVISIONAL ACCEPTANCE.
- E. AT THE END OF THE ESTABLISHMENT PERIOD, INSPECTION SHALL BE MADE AGAIN. ANY PLANT REQUIRED UNDER THIS CONTRACT THAT IS DEAD OR UNSATISFACTORY TO THE LANDSCAPE ARCHITECT OR OWNER SHALL BE REMOVED FROM THE SITE AND REPLACED DURING THE NORMAL PLANTING SEASON.

LAWN SEED NOTES


- LAWN SEED MIX A. PRIOR TO SEEDING, AREA IS TO BE TOPSOILED, FINE GRADED, AND RAKED OF ALL DEBRIS LARGER THAN 1'
- B. THE FOLLOWING SEED MIX SHALL BE SOWN AT THE RATES AS DEPICTED: RED FESCUE 1 1/2 LBS./1,000 SF
- PERENNIAL RYEGRASS 1 LB./1,000 SF KENTUCKY BLUEGRASS 1 1/2 LBS./1,000 SF
- SPREADING FESCUE 1 LB./1,000 SF C. SEED MIX SHALL BE MULCHED WITH SALT HAY OR UNROTTED SMALL GRAIN STRAW AT A RATE OF 2
- TONS/AC OR 90 LBS/1,000 SF D. SEEDING DATES FOR THIS MIXTURE SHALL BE AS FOLLOWS:
- SPRING: APRIL 1 MAY 31 FALL: AUGUST 16 - OCTOBER 31
- E. GERMINATION RATES WILL VARY AS TO TIME OF YEAR FOR SOWING. CONTRACTOR TO IRRIGATE SEEDED AREA UNTIL A STAND OF COVER IS ESTABLISHED AND ACCEPTED BY THE OWNER.

2. GENERAL SEEDING NOTES:


- A. SEEDING SHALL TAKE PLACE IN THE SPRING (APRIL 1 TO JUNE 1) OR THE FALL (SEPTEMBER 1 TO OCTOBER B. ELIMINATE UNWANTED VEGETATION PRIOR TO SEEDING USING A GLYPHOSATE—BASED HERBICIDE PER
- MANUFACTURER'S SPECIFICATIONS. CONTRACTOR TO ENSURE HERBICIDE IS INDICATED FOR USE AROUND WATER C. IT IS RECOMMENDED THAT CONTRACTOR INSTALL SEED MIXTURE USING A NO-TILL TRUAX-TYPE DRILL WHERE
- D. THERE MUST BE CONTINUOUS SOIL MOISTURE FOR 4-6 WEEKS TO ALLOW PROPER GERMINATION.

3. WEED CONTROL / MAINTENANCE


- A. DURING THE ESTABLISHMENT YEAR, CONTRACTOR SHALL MOW SEEDING IF WEED HEIGHT EXCEEDS MEADOW MIX HEIGHT. MOW AT A HEIGHT OF 8"-10". DO NOT MOW CLOSE, AS SOME OF THE MEADOW MIX MAY BE
- B. AFTER THE FIRST GROWING SEASON, AND IF MEADOW MIX IS WELL ESTABLISHED, THE MEADOW MIX SHALL E MOWED ONLY ONCE ANNUALLY. ANNUAL MAINTENANCE MOWING SHALL BE DONE IN LATE WINTER DURING THE
- C. MOW IN DETENTION BASIN DURING DRIER SITE CONDITIONS WHEN SOIL DISTURBANCE WILL NOT OCCUR. MAINTENANCE FOR DETENTION BASIN AND WETLAND TRANSITION AREAS SHALL OCCUR DURING LATE SUMMER (JULY 15 - AUGUST 15) WHEN THE WATER TABLE IS USUALLY AT ITS LOWEST POINT OF THE YEAR. DO NOT MOW IN DETENTION BASIN, WETLAND OR WETLAND TRANSITION AREAS AFTER ESTABLISHMENT OF MEADOW MIX.




DECIDUOUS TREE PLANTING




ORNAMENTAL TREE PLANTING



3 EVERGREEN TREE PLANTING





5 GROUNDCOVER/ PERENNIAL PLANTING

DRAWING RELEASE: No. Date Description 01/04/2019 Permit/Bid Set

PROPOSED CORE AND

SHELL BUILDING:

Convergent East

2 Equity Way

Westlake, OH 44145

JOB NUMBER: 180393.00

LANDSCAPE **DETAILS**


SHEET NUMBER:


SHEET TITLE:

LP501

PLANTING SOIL SPECIFICATIONS

- 1. PLANTING SOIL SHOULD BE FRIABLE, FERTILE, WELL DRAINED, FREE OF DEBRIS, TOXINS, TRASH AND STONES OVER 1/2" DIA., IT SHOULD HAVE A HIGH ORGANIC CONTENT SUITABLE TO SUSTAIN HEALTHY PLANT GROWTH AND SHOULD LOOK AESTHETICALLY PLEASING HAVING NO NOXIOUS ODORS.
- CONTRACTOR SHALL TEST SOILS AND FURNISH SAMPLES UPON REQUEST. PACKAGED MATERIALS SHALL BE UNOPENED BAGS OR CONTAINERS, EACH BEARING A NAME, GUARANTEE, AND TRADEMARK OF THE PRODUCER. MATERIAL COMPOSITION. MANUFACTURER'S CERTIFIED ANALYSIS. AND THE WEIGHT OF THE MATERIALS. SOIL OR AMENDMENT MATERIALS SHALL BE STORED ON SITE TEMPORARILY IN STOCKPILES PRIOR TO PLACEMENT AND SHALL BE PROTECTED FROM INTRUSION OF CONTAMINANTS AND EROSION. AFTER MIXING, SOIL MATERIALS SHALL BE COVERED WITH A TARPAULIN UNTIL TIME OF ACTUAL USE.
- 3. THE FOLLOWING TESTING SHOULD BE PERFORMED AND RESULTS GIVEN TO THE LANDSCAPE ARCHITECT FOR APPROVAL BEFORE INSTALLATION: a. PARTICLE SIZE ANALYSIS - LOAMY SAND: 70-85% SAND, 15-30% SILT AND CLAY
- b. FERTILITY ANALYSIS: pH (5.5-6.5), SOLUBLE SALTS (0.25-0.60 MMHOS/CM), NITRATE, PHOSPHATE, POTASSIUM, CALCIUM AND MAGNESIUM c. ORGANIC MATTER CONTENT: 7-10%
- d. TOXIC SUBSTANCE ANALYSIS e. MATERIAL DRAINAGE RATE: 60% PASSING IN 2 MINUTES, 40% RETAINED
- 4. ORGANIC MATTER AS A SOIL AMENDMENT:
- a. LEAF MOLD WITH 60-90% ORGANIC CONTENT BY WEIGHT. b. SHREDDED LEAF LITTER, COMPOSTED FOR A MINIMUM OF 1 YR. SHOULD BE FREE OF DEBRIS, STONES OVER 1/2", WOOD CHIPS OVER 1".
- 5. SOIL AMENDMENT FOR PLANT MATERIAL: SOIL IN BEDS AND PLANTING ISLANDS OTHER THAN BACKFILL MATERIAL AND TOPSOIL, SHOULD BE FRIABLE, WELL DRAINED, AND FREE OF DEBRIS, INCLUDING STONES AND TRASH. -AMENDMENTS FOR BACKFILL IN TREE AND SHRUB PITS:
- A. GROUND LIMESTONE (WITH A MIN. OF 88% OF CALCIUM AND MAGNESIUM CARBONATES) USED PENDING RESULTS OF SOIL ANALYSIS.
- BRING pH LEVELS TO 5.5 MIN. TO 6.5 FOR NON-ERICACEOUS PLANTS BRING pH LEVELS TO 4.5 MIN. TO 5.5 FOR ERICACEOUS PLANTS
- B. TERRA-SORB BY 'PLANT HEALTH CARE' 800-421-9051 (SEE MANUFACTURER RECOMMENDATIONS) USED IN PLANTER BACKFILL MIXTURE WITH TREES AND SHRUBS. C. MYCOR-ROOT SAVER BY 'PLANT HEALTH CARE' 800-421-9051 (SEE MANUFACTURER RECOMMENDATIONS) USED IN BACKFILL MIXTURE WITH TREES.





PROJECT NAME AND LOCATION CONVERGENT EAST

OWNER NAME AND ADDRESS

WESTLAKE, OHIO 44145

SITE DESCRIPTION

SOIL TYPES

THIS PROJECT WILL CONSIST OF CONSTRUCTING AN OFFICE BUILDING, PARKING LOT AND ON SITE UTILITIES. SOIL DISTURBING ACTIVITIES WILL INCLUDE: INSTALLING A STABILIZED CONSTRUCTION ENTRANCE, PERIMETER, AND OTHER EROSION AND SEDIMENT CONTROLS; DEMOLITION, GRADING, STORM SEWER', AND UTILITIES; AND PREPARATION FOR FINAL PLANTING AND SEEDING.

THE SITE IS APPROXIMATELY 2.87 ACRES OF DISTURBANCE BY CONSTRUCTION ACTIVITIES.

INCLUDING DUMPSTER, CEMENT TRUCK WASHOUT, AND VEHICLE REFUELING AREAS.

A: As — Allis silt loam
B: Ua — Udorthents, loamy
16% OF SITE

THE CONTRACTOR SHALL USE EROSION CONTROL MEASURES AS NECESSARY TO PREVENT SEDIMENT MOVEMENT INTO AREAS DESIGNATED AS WETLANDS, STREAMS, OR WATER BODIES.

NO SOLID OR LIQUID WASTE SHALL BE DISCHARGED INTO STORM WATER RUNOFF. THE CONTRACTOR SHALL USE THE INDICATED AREA DESIGNATED FOR THE STORAGE OR DISPOSAL OF SOLID, SANITARY, AND TOXIC WASTES,

CAST IRON CATCH BASINS, GRATES, AND INLET COVERS WITH MESSAGES SUCH AS "DUMP NO WASTE, DRAINS TO WATERWAYS" SHALL BE UTILIZED AS A NON-STRUCTURAL BEST MANAGEMENT PRACTICE THAT PROMOTES POLLUTION PREVENTION AND CONSERVATION AWARENESS. ALL CATCH BASIN GRATES AND INLET COVERS SHALL BE SPECIFIED WITH AN EQUIVALENT MESSAGE.

PRIOR LAND USE

THE SITE WAS PREVIOUSLY DEVELOPED AS A PARKING LOT.

SEQUENCE OF MAJOR ACTIVITIES

ALL NECESSARY EROSION, SEDIMENT, NON-SEDIMENT POLLUTANT CONTROLS, STORM WATER MANAGEMENT PRACTICES OR FACILITIES, AND POST-CONSTRUCTION BEST MANAGEMENT PRACTICES ARE TO BE EMPLOYED DURING EACH OPERATION OF THE SEQUENCE.

THE ORDER OF ACTIVITIES WILL BE AS FOLLOWS:

1. INSTALL STABILIZED CONSTRUCTION ENTRANCE AND PERIMETER CONTROLS (SILT FENCE, COMPOST FILTER SOCK, INLET PROTECTION). 2. CLEAR AND GRUB TREES, BRUSH AND STUMPS AS NECESSARY TO ACCOMPLISH CONSTRUCTION. STRIP AND STOCKPILE TOPSO

S STABILIZE DENUDED AREAS AND STOCKPILES WITHIN 7 DAYS OF LAST CONSTRUCTION ACTIVITY IN THAT AREA. 4. COMMENCE EARTHWORK ACTIVITIES. 5. INSTALL STORMWATER MANAGEMENT SYSTEMS PER PLANS.

6. INSTALL UTILITIES, STORM SEWER, ETC. 7. APPLY STONE BASE TO ROADWAYS 8. COMPLETE GRADING AND INSTALL PERMANENT SEEDING.

COMPLETE FINAL PAVING. 10. ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED UPON PERMANENT STABILIZATION. RE—SEED ANY DISTURBED AREAS.

OTHER EROSION CONTROL ITEMS MAY BE NECESSARY DUE TO ENVIRONMENTAL CONDITIONS.

NAME OF RECEIVING WATERS

ACTIVITIES.

THE SITE WILL DRAIN TO AN ON-SITE STORM SYSTEM WHICH DISCHARGES TO A TRIBUTARY OF PORTER CREEK.

SITE DESCRIPTION

NOTICE OF INTENT (NOI) MUST BE SUBMITTED TO THE OHIO EPA FOR NPDES PERMIT 21 DAYS PRIOR TO THE START OF CLEARING AND GRADING. ALL CONSTRUCTION ACTIVITIES MUST COMPLY WITH ALL LOCAL EROSION AND SEDIMENT CONTROL REGULATIONS.

ALL EROSION AND SEDIMENT CONTROL PRACTICES MUST MEET THE STANDARDS AND SPECIFICATIONS OF THE CURRENT EDITION OF THE OHIO RAINWATER AND LAND DEVELOPMENT MANUAL. PERIMETER CONTROLS SHALL BE IMPLEMENTED AS A FIRST STEP AND SHALL CONTINUE TO FUNCTION UNTIL UPLAND AREAS ARE STABILIZED.

REGULAR INSPECTION AND MAINTENANCE WILL BE PROVIDED FOR ALL EROSION AND SEDIMENT CONTROL PRACTICES. INSPECTIONS ARE TO BE PERFORMED UNTIL THE NOTICE OF TERMINATION (NOT) IS FILED. PERMANENT RECORDS OF MAINTENANCE AND INSPECTIONS MUST BE KEPT THROUGHOUT THE CONSTRUCTION PERIOD AND FOR 3 YEARS AFTER THE (NOT) IS FILED WITH THE OHIO EPA. INSPECTIONS MUST BE MADE A MINIMUM OF ONCE EVERY 7 DAYS AND IMMEDIATELY AFTER STORM EVENTS GREATER THAN 0.5 INCHES OF RAIN IN A 24 HOUR PERIOD. PROVIDE NAME OF INSPECTOR, MAJOR OBSERVATIONS, DATE OF INSPECTION, AND CORRECTIVE MEASURES TAKEN.

AN OFF-SITE BORROW OR SPOIL AREAS SHALL BE COVERED BY A SEPARATE (NOI) THESE PLANS SHALL NOT BE USED FOR ANY OFF SITE

GENERAL NOTES

AS INDICATED IN THE SEQUENCE OF MAJOR ACTIVITIES, STABILIZED CONSTRUCTION ENTRANCES, SILT FENCE, AND SEDIMENTS BASINS WILL BE CONSTRUCTED PRIOR TO CLEANING OR GRADING OF ANY OTHER PORTIONS OF THE SITE. AREAS WHERE CONSTRUCTION ACTIVITY TEMPORARILY CEASES FOR MORE THAN 14 DAYS WILL BE STABILIZED WITH A TEMPORARY SEED AND MULCH WITHIN 7 DAYS OF THE LAST DISTURBANCE. ONCE CONSTRUCTION ACTIVITY CEASES PERMANENTLY IN AN AREA, THAT AREA WILL BE STABILIZED WITH PERMANENT SEED AND MULCH. AFTER THE ENTIRE SITE IS STABILIZED, THE ACCUMULATED SEDIMENT WILL BE REMOVED FROM THE BASIN.

DISTURBED AREAS THAT ARE TO REMAIN DORMANT FOR OVER 1 YEAR OR AT FINAL GRADE SHALL HAVE PERMANENT EROSION CONTROLS APPLIED WITHIN 7 DAYS.

TIMING OF CONTROLS/MEASURES

NON-STRUCTURAL PRESERVATION METHODS

EROSION CONTROL PRACTICES

PERMANENT STABILIZATION

PRACTICES SHALL BE USED WHICH PRESERVE THE EXISTING NATURAL CONDITION AS MUCH AS POSSIBLE. SUCH PRACTICES MAY INCLUDE: PRESERVING RIPARIAN AREAS ADJACENT TO SURFACE WATERS OF THE STATE, PRESERVING EXISTING VEGETATION AND VEGETATIVE BUFFER STRIPS, PHASING CONSTRUCTION OPERATIONS IN ORDER TO MINIMIZE THE AMOUNT OF DISTURBED LAND AT ANY ONE TIME, AND DESIGNATION OF TREE PRESERVATION AREAS OR OTHER PROTECTIVE CLEARING OR GRUBBING PRACTICES. THE RECOMMENDED BUFFER THAT OPERATORS SHOULD LEAVE UNDISTURBED ALONG A \$URFACE WATER OF THE STATE IS 25 FEET AS MEASURED FROM THE ORDINARY HIGH WATER MARK OF THE SURFACE WATER.

ALL DISTURBED AREAS OF THE SITE SHALL BE PROTECTED BY STABILIZATION PRACTICES. SUCH PRACTICES MAY INCLUDE: TEMPORARY SEEDING, PERMANENT SEEDING MULCHING, MATTING, SOD STABILIZATION, VEGETATIVE BUFFER STRIPS, PHASING OF CONSTRUCTION OPERATIONS, USE OF CONSTRUCTION ENTRANCES, AND THE USE OF ALTERNATIVE GROUND COVER.

THE TIMING SPECIFICATIONS FOR THE PERMANENT SEED CAN BE FOUND IN THE TABLE BELOW. THE PERMANENT SEED SHALL BE APPLIED AS PER THE TEMPORARY SEEDING SPECIFICATIONS. NOTE THAT 70% VEGETATIVE DENSITY IS REQUIRED ON ALL DISTURBED SOIL AREAS FOR STABILIZATION.

AREA REQUIRIING PERM	ANENT STABILIZATION	TIME FRAME TO APPLY EROSION CONTROLS
ANY AREA THAT WILL I	IE DORMANT FOR 1 YEAR OR MORE.	WITHIN SEEN DAYS OF THE MOST RECENT DISTURBANCE.
ANY AREAS WITHIN 50 AT FINAL GRADE.	FEET OF SURFACE WATER OF THE STATE AND	WITHIN TWO DAYS OF REACHING FINAL GRADE.
ANY OTHER AREAS AT	FINAL GRADE.	WITHIN SEVEN DAYS OF REACHING FINAL GRADE WITHIN THAT AREA

TEMPORARY STABILIZATION

THE TIMING SPECIFICATIONS FOR THE TEMPORARY SEED CAN BE FOUND IN THE TABLE BELOW. THE TEMPORARY SEED SHALL BE APPLIED AS PER THE TEMPORARY SEEDING SPECIFICATIONS, AREAS OF THE SITE WHICH ARE TO BE PAVED WILL BE TEMPORARILY STABILIZED BY APPLYING AGGREGATE BASE UNTIL ASPHALT AND CONCRETE PAVEMENT CAN BE APPLIED. NOTE THAT 70% VEGETATIVE DENSITY IS REQUIRED ON ALL DISTURBED SOIL AREAS FOR STABILIZATION.

AREA REQUIRIING TEMP	ORARY STABILIZATION	TIME FRAME TO APPLY EROSION CONTROLS
ANY DISTURBED AREAS STATE AND NOT AT FIN	WITHIN 50 FEET OF A SURFACE WATER OF THE NAL GRADE.	WITHIN TWO DAYS OF THE MOST RECENT DISTURBANCE IF THE THE AREA WILL REMAIN IDLE FOR MORE THAN 14 DAYS.
BE DORMANT FOR MOR	N ACTIVITIES, ANY DISTURBED AREAS THAT WILL E THAN 14 DAYS BUT LESS THAN 1 YEAR, AND F A SURFACE WATER OF THE STATE.	WITHIN SEVEN DAYS OF THE MOST RECENT DISTURBANCE WITHIN THE AREA.
		FOR RESIDENTIAL SUBDIVISION, DISTURBED AREAS MUST BE STABILIZED AT LEAST SEVEN DAYS PRIOR TO TRANSFER OF PERMIT COVERAGE FOR THE INDIVIDUAL LOT(S).
DISTURBED AREAS THA	T WILL BE IDLE OVER WINTER.	PRIOR TO ONSET OF WINTER WEATHER.

WHERE VEGETATIVE STABILIZATION TECHNIQUES MAY CAUSE STRUCTURAL INSTABILITY OR ARE OTHERWISE UNOBTAINABLE, ALTERNATIVE STABILIZATION TECHNIQUES MUST BE EMPLOYED.

PERMANENT STABILIZATION OF CONVEYANCE CHANNELS

CHARACTERISTICS AND FUNCTIONS ARE MAINTAINED AND PROTECTED.

OPERATORS SHALL UNDERTAKE SPECIAL MEASURES TO STABILIZED CHANNELS AND OUTFALLS AND PREVENT EROSIVE FLOWS. MEASURES MAY INCLUDE: SEEDING, DORMANT SEEDING, MULCHING, EROSION CONTROL MATTING, SODDING, RIPRAP, NATURAL CHANNEL DESIGN WITH BIOENGINEERING TECHNIQUES OR ROCK CHECK DAMS.

RUN-OFF CONTROL PRACTICES

MEASURES SHALL BE IMPLEMENTED WHICH CONTROL THE FLOW OF RUN-OFF FROM DISTURBED AREAS SO AS TO PREVENT EROSION FROM OCCURRING. SUCH PRACTICES MAY INCLUDE: ROCK CHECK DAMS, PIPE SLOPE DRAINS, DIVERSIONS TO DIRECT FLOW AWAY FROM EXPOSED SOILS, AND PROTECTIVE GRADING PRACTICES. THESE PRACTICES SHALL DIVERT RUNOFF AWAY FROM DISTURBED AREAS AND STEEP SLOPES WHERE PRACTICABLE VELOCITY DISSIPATION DEVICES SHALL BE PLACED AT DISCHARGE LOCATIONS ALONG THE LENGTH OF THE LENGTH OF ANY OUTFALL CHANNEL TO PROVIDE NON—EROSIVE FLOW VELOCITY FROM THE STRUCTURE TO A WATER COURSE SO THAT THE NATURAL PHYSICAL AND BIOLOGICAL

SEDIMENT CONTROL PRACTICES

STRUCTURAL PRACTICES SHALL BE USED TO CONTROL EROSION AND TRAP SEDIMENT FROM A SITE REMAINING DISTURBED FOR MORE THAN 14 DAYS, WHICH STORE RUN-OFF ALLOWING SEDIMENTS TO SETTLE AND/OR DIVERT FLOWS AWAY FROM EXPOSED SOILS OR OTHERWISE LIMIT RUNOFF FROM EXPOSED AREAS. SUCH PRACTICES MAY INCLUDE, BUT AMONG OTHERS: SEDIMENT SETTLING PONDS, SILT FENCES, EARTH DIVERSION DIKES OF CHANNELS WHICH DIRECT RUN—OFF TO A SEDIMENT SETTLING POND, AND STORM DRAIN INLET PROTECTION. ALL SEDIMENT CONTROL PRACTICES MUST BE CAPABLE OF OF PONDING RUN-OFF IN ORDER TO BE CONSIDERED FUNCTIONAL. EARTH DIVERSION DIKES OR CHANNELS ALONE ARE NOT

CONSIDERED A SEDIMENT CONTROL PRACTICE UNLESS THOSE ARE USED IN CONJUNCTION WITH A SEDIMENT SETTLING POND. PRACTICES IMPLEMENTED IN THIS PLAN:

COMPOST FILTER SOCKS INLET PROTECTION OTHER

SEDIMENT CONTROL PRACTICES SHALL BE FUNCTIONAL THROUGHOUT THE COURSE OF EARTH DISTURBING ACTIVITY. SEDIMENT BASINS AND PERIMETER SEDIMENT BARRIERS SHALL BE IMPLEMENTED PRIOR TO GRADING AND WITHIN SEVEN DAYS FROM THE START OF GRUBBING. THEY SHALL CONTINUE TO FUNCTION UNTIL THE UP—SLOPE DEVELOPMENT AREA IS RE—STABILIZED. AS CONSTRUCTION PROGRESSES AND THE TOPOGRAPHY IS ALTERED, APPROPRIATE CONTROLS MUST BE CONSTRUCTED OR EXISTING CONTROLS ALTERED TO ADDRESS THE CHANGING DRAINAGE PATTERNS. SILT FENCE AND COMPOST FILTER SOCK

SHEET FLOW RUN-OFF FROM DENUDED AREAS SHALL BE INTERCEPTED BY SILT FENCE OR COMPOST FILTER SOCK TO PROTECT ADJACENT PROPERTIES AND WATER RESOURCES FROM SEDIMENT TRANSPORTED VIA SHEET FLOW. WHERE INTENDED TO PROVIDE SEDIMENT CONTROL, SILT FENCE AND COMPOST FILTER SOCK SHALL BE PLACED ON A LEVEL CONTOUR DOWN SLOPE OF THE DISTURBED AREA.

INLET PROTECTION SHALL BE USED TO MINIMIZE SEDIMENT LADEN WATER ENTERING THE ACTIVE STORM SEWER SYSTEM.

SURFACE WATERS OF THE STATE PROTECTION

F CONSTRUCTION ACTIVITIES DISTURB AREAS ADJACENT TO SURFACE WATERS OF THE STATE, STRUCTURAL PRACTICES SHALL BE IMPLEMENTED ON SITE TO PROTECT ALL ADJACENT SURFACE WATERS OF THE STATE FROM THE IMPACTS OF SEDIMENT RUNOFF. NO STRUCTURAL SEDIMENT CONTROLS (E.G., THE INSTALLATION OF SILT FENCE OR A SEDIMENT SETTLING SEDIMENT POND) SHALL BE USED IN A SURFACE WATER OF THE STATE. FOR ALL CONSTRUCTION ACTIVITIES IMMEDIATELY ADJACENT TO SURFACE WATERS OF THE STATE, IT IS RECOMMENDED THAT A SETBACK OF AT LEAST 25 FEET, AS MEASURED FROM THE ORDINARY HIGH WATER MARK OF THE SURFACE WATER, BE MAINTAINED IN ITS NATURAL STATE AS A PERMANENT

SEDIMENT AND EROSION CONTROLS

ANTICIPATED IMPACTS ON WATER QUALITY, ETC. (REFERENCE PAGE 19 OF OHIO EPA'S NPDES PERMIT) (APRIL 23, 2018)

POST-CONSTRUCTION PRACTICES SHALL PROVIDE FOR PERPETUAL MAINTENANCE OF RUN-OFF QUALITY AND QUANTITY. REFER TO MAINTENANCE AND INSPECTION PROCEDURE SECTION.

RUN-OFF QUANTITY WILL BE CONTROLLED BY THE ON-SITE DETENTION SYSTEM. RUN-OFF QUALITY DURING CONSTRUCTION WILL BE MAINTAINED BY PERIMETER CONTROLS.

REFER TO DESCRIPTION OF POST-CONSTRUCTION BMP'S LISTED BELOW. MAINTENANCE PLAN SHALL ENSURE THAT POLLUTANTS COLLECTED WITHIN STRUCTURAL POST-CONSTRUCTION PRACTICES WILL BE DISPOSED OF IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REGULATIONS.

POST-CONSTRUCTION BMP WATER QUALITY DESIGN

THE OHIO EPA; S GENERAL PERMIT FOR CONSTRUCTION REQUIRES THE IMPLEMENTATION OF POST-CONSTRUCTION BMP'S ON ALL PROJECTS WHERE THE LARGER COMMON PLAN OF DEVELOPMENT OR SITE DISTURBS ONE OR MORE ACRES.

FOR NEW DEVELOPMENT THE OHIO EPA'S GENERAL CONSTRUCTION PERMIT REQUIRES THAT STRUCTURAL POST-CONSTRUCTION BMP'S BE PROVIDED ON ANY PROJECTS WHERE THE LARGER COMMON PLAN OF DEVELOPMENT OR SITE WILL RESULT IN 2 OR MORE ACRES OF DISTURBANCE. STRUCTURAL BMP'S MUST PROVIDE EXTENDED DETENTION OF THE WATER QUALITY VOLUME (WQV). IN ADDITION, AND EXTRA 20% OF THE (WQV) MUST BE PROVIDED WITHIN THE AREA OF THE BMP WHERE POLLUTANTS WILL ACCUMULATE TO PROVIDE STORAGE FOR THESE POLLUTANTS.

FOR REDEVELOPMENT PROJECTS, THE OHIO EPA'S GENERAL PERMIT REQUIRES EITHER (A) A 20% NET REDUCTION OF SITE IMPERVIOUS AREA, (B) STRUCTURAL BMP'S BE PROVIDED TO TREAT 20% OF THE WQV, OR (C) A COMBINATION OF (A) AND (B) THAT HAS THE SAME NET EFFECT. NEW DEVELOPMENT (SYSTEM B)

WQV = WATER QUALITY VOLUME IN ACRE-FEET TOTAL SITE WQV (REQUIRED) = 82 CUBIC FEET

REDEVELOPMENT (SYSTEM A)

WQV = P*A*[(Rv1*0.2)+(Rv2-Rv1)]/12WQV = WATER QUALITY VOLUME IN ACRE-FEET TOTAL SITE WQV (REQUIRED) = 825 CUBIC FEET

TOTAL SITE WQV (PROVIDED) = 907 CUBIC FEET

POST-CONSTRUCTION STORM WATER MANAGEMENT

NON-SEDIMENT POLLUTANT CONTROLS

NON-SEDIMENT POLLUTANT SOURCES, WHICH MAY BE PRESENT ON A CONSTRUCTION SITE, INCLUDE PAVING OPERATIONS, CONCRETE WASHOUT STRUCTURE PAINTING, STRUCTURE CLEANING, DEMOLITION DEBRIS DISPOSAL, DRILLING AND BLASTING OPERATIONS, MATERIAL STORAGE, SLAG, SOLID WASTE, HAZARDOUS WASTE, CONTAMINATED SOILS, SANITARY AND SEPTIC WASTES, VEHICLE FUELING AND MAINTENANCE ACTIVITIES, AND LANDSCAPING OPERATIONS.

HANDLING OF TOXIC OR HAZARDOUS MATERIALS

ALL HAZARDOUS AND TOXIC WASTE MATERIALS WILL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR STATE REGULATION OR BY THE MANUFACTURER, THE INDIVIDUAL WHO MANAGES THE DAY-TO-DAY SITE OPERATIONS WILL BE RESPONSIBLE FOR SEEING THAT THESE PRACTICES ARE FOLLOWED. NO TOXIC OR HAZARDOUS WASTES SHALL BE DISPOSED OF INTO STORM DRAINS, SEPTIC TANKS, OR BY BURYING, BURNING, OR MIXING

WASTE DISPOSAL

CONTAINERS SHALL BE PROVIDED FOR THE PROPER COLLECTION OF ALL WASTE MATERIAL INCLUDING CONSTRUCTION DEBRIS, TRASH, PETROLEUM PRODUCTS AND ANY HAZARDOUS MATERIALS USED ON-SITE. CONTAINERS SHALL BE COVERED AND NOT LEAKING. ALL WASTE MATERIAL SHALL BE DISPOSED OF AT FACILITIES APPROVED FOR THAT MATERIAL, CONSTRUCTION DEMOLITION AND DEBRIS (CD&C) WASTE MUST BE DISPOSED OF AT AN OHIO EPA APPROVED CD&C LANDFILL, NO CONSTRUCTION RELATED WASTE MATERIALS ARE TO BE BURIED ON-SITE. BY EXCEPTION, CLEAN-FILL (BRICKS, HARDENED CONCRETE, SOIL) MAY BE UTILIZED IN A WAY WHICH DOES NOT ENCROACH UPON NATURAL WETLANDS, STREAMS OR FLOODPLAINS OR RESULT IN THE CONTAMINATION OF WATERS OF THE STATE.

ALL SANITARY WASTE WILL BE COLLECTED FROM THE PORTABLE UNITS AS NECESSARY BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR, AS REQUIRED BY LOCAL REGULATION.

ALL BRICKS, HARDENED CONCRETE, AND SOIL WASTE MUST BE FREE FROM CONTAMINATION WHICH MAY LEACH CONSTITUENTS TO WATERS OF THE STATE. ANY CLEAN CONSTRUCTION WASTES THAT WILL BE DISPOSED INTO THE PROPERTY MUST MEET ALL LOCAL, CITY, AND STATE REGULATIONS.

ALL CONSTRUCTION AND DEMOLITION DEBRIS WASTE WILL BE DISPOSED OF IN AN OHIO EPA APPROVED CONSTRUCTION AND DEMOLITION DEBRIS LANDFILL AS REQUIRED BY OHIO REVISED CODE 3714.

OFF-SITE VEHICLE TRACKING SEDIMENT SHALL BE MINIMIZED. CONSTRUCTION VEHICLES ARE LIMITED TO THE CONSTRUCTION ACCESS ROADS NOTED ON THE PLAN. A STABILIZED CONSTRUCTION ENTRANCE WILL BE PROVIDED TO HELP REDUCE VEHICLE TRACKING OF SEDIMENTS. ALL PAVED STREETS ADJACENT TO THE SITE WILL BE SWEPT AS NECESSARY TO REMOVE ANY EXCESS MUD, DIRT, AND ROCK TRACKED FROM THE SITE. DUMP TRUCKS HAULING MATERIAL FROM THE CONSTRUCTION SITE WILL BE COVERED WITH A TARPAULIN.

THE CONTRACTOR SHALL ONLY PERFORM ON-SITE OPEN BURNING AS A MEANS OF WASTE DISPOSAL AS ALLOWED PER LOCAL, STATE, AND FEDERAL

REGULATIONS.

CONSTRUCTION TRAFFIC MUST ENTER AND EXIT THE SITE AT THE STABILIZED CONSTRUCTION ENTRANCE(S). WATER TRUCKS WILL BE USED AS NEEDED DURING CONSTRUCTION TO REDUCE DUST GENERATION. DUST CONTROL MUST BE PROVIDED TO A DEGREE THAT IS ACCEPTABLE AND IN COMPLIANCE WITH APPLICABLE LOCAL AND STATE DUST CONTROL REGULATIONS. AFTER CONSTRUCTION, THE SITE WILL BE STABILIZED (AS DESCRIBED ELSEWHERE IN THIS PLAN), WHICH WILL REDUCE THE POTENTIAL FOR DUST GENERATION.

PRODUCT SPECIFIC PRACTICES
THE FOLLOWING SPECIFIC PRACTICES WILL BE FOLLOWED ON—SITE:

FERTILIZERS WILL BE APPLIED ONLY IN THE MINIMUM AMOUNTS RECOMMENDED BY THE MANUFACTURER. ONCE APPLIED. FERTILIZER WILL BE WORKED INTO THE SOIL TO LIMIT EXPOSURE TO STORM WATER. STORAGE WILL BE IN A COVERED SHED. THE CONTENTS OF ANY PARTIALLY USED BAGS OF FERTILIZER WILL BE TRANSFERRED TO A SEALABLE PLASTIC BIN TO AVOID SPILLS. PETROLEUM PRODUCTS

ALL ON-SITE VEHICLES WILL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTATIVE MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE. PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED. ANY ASPHALT SUBSTANCES USED ON-SITE WILL BE APPLIED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS. ALL CONTAMINATED SOILS MUST BE TREATED AND/OR DISPOSED OF IN OHIO EPA APPROVED SOLID WASTE MANAGEMENT FACILITIES OR HAZARDOUS WASTE TREATMENT, STORAGE OR DISPOSAL FACILÍTIES.

THE SITE SUPERINTENDENT RESPONSIBLE FOR THE DAY-TO-DAY SITE OPERATIONS WILL BE THE SPILL PREVENTION AND CLEAN UP COORDINATOR. ALL CONTAINERS WILL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE. EXCESS PAINT WILL NOT BE DISCHARGED TO THE STORM SEWER SYSTEM BUT WILL BE PROPERLY DISPOSED OF ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS OR STATE AND LOCAL REGULATIONS.

CONCRETE TRUCKS WILL NOT BE ALLOWED TO WASH OUT OR DISCHARGE SURPLUS CONCRETE OR DRUM WASH WATER ON THE SITE EXCEPT IN AREAS SPECIFICALLY DESIGNATED BY THE INDIVIDUAL WHO MANAGES THE DAY-TO-DAY SIGHT OPERATIONS.

OTHER CONTROLS

PROPOSED CORE AND SHELL BUILDING:

Convergent East

2 Equity Way Westlake, OH 44145

JOB NUMBER: **180393.00**

No. Date

01/04/2019

DRAWING RELEASE:

Permit/Bid Set

SESC DETAILS

SHEET NUMBER:

SHEET TITLE:

CE501

10/24/2018

TYPICAL MAINTENANCE ACTIVITY FOR UNDERGROUND DETENTION AND WATER QUALITY SYSTEM THE OWNER WILL BE RESPONSIBLE FOR THE LONG TERM MAINTENANCE OF THE UNDERGROUND DETENTION AND WATER QUALITY SYSTEM, THE OWNER SHALL FOLLOW THE MAIN TENANCE SPECIFICATIONS PROVIDED ON PAGE 27 OF "MAINTAINING STORMWATER CONTROL MEASURES: GUIDANCE FOR PRIVATE OWNERS AND OPERATORS". LONG TERM MAINTENANCE PLAN THIS IS A SUGGESTED SCHEDULE ONLY; VEGETATIVE NEEDS MAY VARY DEPENDING ON SITE CONDITIONS. SOME MAINTENANCE NEEDS INCLUDE: -PH ADJUSTMENT (AS REQUIRED) -PEST CONTROL -RESEEDING (IN PARTICULAR AFTER MAINTENANCE OF FOREBAY AND MICRO POOL IF DISTURBANCES HAVE OCCURRED) -THATCH AN WEED REMOVAL MATERIAL MANAGEMENT PRACTICES THATCH REMOVAL INCLUDES THE FOLLOWING UNWANTED WOODY SEEDLINGS IN SHORELINE AREAS: THE FOLLOWING ARE THE MATERIAL MANAGEMENT PRACTICES THAT WILL BE USED TO REDUCE THE RISK OF SPILLS OR OTHER ACCIDENTAL EXPOSURE -COTTONWOOD (POULOUS DELTOIDES) OF MATERIALS AND SUBSTANCES TO STORMWATER RUN-OFF. -WILLOW (SALIX SPP.) -SILVER MAPLE (ACER SACCHARINUM) WEED REMOVAL INCLUDES THE FOLLOWING SPECIES DETRIMENTAL TO WETLAND PLANTINGS: -COMMON REED (PHRAGMITES AUSTRALIS) THE FOLLOWING GOOD HOUSEKEEPING PRACTICES WILL BE FOLLOWED ON-SITE DURING THE CONSTRUCTION PROJECT: -CATTAILS (TYPHA SPP.) -AN EFFORT WILL BE MADE TO STORE ONLY ENOUGH PRODUCT REQUIRED TO DO THE JOB. -PURPLE LOOSESTRIFE (LYTHRUM SALICARIA) -ALL MATERIALS STORED ON-SITE WILL BE STORED IN A NEAT, ORDERLY MANNER IN THEIR APPROPRIATE CONTAINERS AND, IF POSSIBLE, UNDER A ROOF OR OTHER ENCLOSURE. WHEN REMOVING THE PURPLE LOOSESTRIFE IT IS IMPORTANT TO REMOVE THE LARGE ROOT SYSTEMS AS WELL AS THE PLANT PRIOR TO FLOWERING -PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL MANUFACTURER'S LABEL. (JUNE THROUGH SEPTEMBER). THE PLANT AND ITS PARTS SHOULD BE IMMEDIATELY PLACED IN A BAG TO PREVENT FURTHER SPREAD OF THE -SUBSTANCES WILL NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED BY THE MANUFACTURER. SPECIES. IF THIS PROCEDURÉ IS NOT POSSIBLE, REGULARLY REMOVE THE FLOWER HEADS BEFORE SEEDS ARE DISPERSED. -WHENEVER POSSIBLE, ALL OF A PRODUCT WILL BE USED UP BEFORE DISPOSING OF THE CONTAINER. -MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL WILL BE FOLLOWED. IF WEED GROWTH EXCEEDS 10" IN HEIGHT IN SEEDED AREAS TRIM OR MOW TO 4". DO NOT CUT AREAS WHERE LIVE PLANTS WERE INSTALLED. -THE SITE SUPERINTENDENT WILL INSPECT DAILY TO ENSURE PROPER USE AND DISPOSAL OF MATERIALS ON-SITE. HAZARDOUS PRODUCTS THESE PRACTICES ARE USED TO REDUCE THE RISKS ASSOCIATED WITH HAZARDOUS MATERIALS: VEGETATION MAINTENANCE PLAN -PRODUCTS WILL BE KEPT IN ORIGINAL CONTAINERS UNLESS THEY ARE NOT RESEALABLE. -ORIGINAL LABELS AND MATERIAL SAFETY DATA WILL BE RETAINED; THE CONTAIN IMPORTANT PRODUCT INFORMATION. -IF SURPLUS PRODUCT MUST BE DISPOSED OF, MANUFACTURERS' OR LOCAL AND STATE RECOMMENDED METHODS FOR PROPER DISPOSAL WILL BE FOLLOWED. J | F | M | A | M | J | J | A | S | O | N | D | STABILIZATION TYPE PERMANENT SEEDING EMERGENCY CONTACT INFORMATION DORMANT SEEDING IN THE EVENT OF A SPILL OF PETROLEUM FUEL OVER 25 GALLONS, THE CONTRACTOR SHALL CONTACT THE OHIO EPA AT 1-800-282-9378 AND ** ** ** ** ** ** TEMPORARY SEEDING THE LOCAL FIRE DEPARTMENT AT 1-440-986-5901 WITHIN 30 MINUTES. SODDING MULCHING SPILL CONTROL PRACTICES IN ADDITION TO THE GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTIONS OF THIS PLAN, THE * - IRRIGATION NEEDED FOLLOWING PRACTICES WILL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP: ** - IRRIGATION NEEDED FOR 2-3 WEEKS AFTER SOD IS APPLIED -MANUFACTURERS' RECOMMENDATION METHODS FOR SPILL CLEANUP POSTED SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES. -MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREA ON-SITE. EQUIPMENT AND SOIL PROTECTION CHART MATERIALS WILL INCLUDE BUT NOT BE LIMITED TO BROOMS, DUST PANS, MOPS, RAGS, GLOVES, GOGGLES, KITTY LITTER, SAND, SAWDUST, AND PLASTIC AND METAL TRASH CONTAINERS SPECIFICALLY FOR THIS PURPOSE. -ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY. STORM SEWER **TASKS** -THE SPILL AREA WILL BE KEPT WELL VENTILATED AND PERSONNEL WILL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM UNDERGROUND CONTROL **SCHEDULE** HANNELS CONTACT WITH A HAZARDOUS SUBSTANCE. DETENTION PAVED AREAS SYSTEM CASTINGS -SPILLS OF TOXIC OR HAZARDOUS MATERIAL WILL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL GOVERNMENT AGENCY, REGARDLESS OF INSPECT FOR SEDIMENT ACCUMULATION \mathbf{X} \mathbf{X} \mathbf{X} WEEKLY -THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM RECURRING AND HOW TO CLEAN UP THE SPILL IF THERE IS ANOTHER ONE. A DESCRIPTION OF THE SPILL, WHAT CAUSED IT, AND THE CLEANUP MEASURES WILL ALSO AS NEEDED* AND PRIOR REMOVAL OF SEDIMENT ACCUMULATION BE INCLUDED. TO TURNOVER INSPECT FOR FLOATABLES AND DEBRIS X QUARTERLY QUARTERLY AND CLEANING OF FLOATABLES AND DEBRIS AT TURNOVER SPILL PREVENTION INSPECTION FOR EROSION WEEKLY AS NEEDED* AND PRIOR REESTABLISH PERMANENT VEGETATION ON ERODED SLOPES TO TURNOVER EROSION AND SEDIMENT CONTROL AND MAINTENANCE PRACTICES AS NEEDED* AND PRIOR CLEAN STREETS THESE ARE THE INSPECTION AND MAINTENANCE PRACTICES THAT WILL BE USED TO MAINTAIN EROSION AND SEDIMENT: TO TURNOVER -CONSTRUCTION ACTIVITIES SHALL BE SCHEDULE SUCH THAT A MINIMUM AREA OF THE SITE IS DISTURBED AT ANY TIME, CONSTRUCTION AS NEEDED* AND PRIOR MOWING OPERATIONS SHALL BE SCHEDULE AND PERFORMED SO THAT PREVENTATIVE SOIL EROSION AND TEMPORARY STABILIZATION MEASURES ARE IN TO TURNOVER PLACE IMMEDIATELY FOLLOWING BACKFILLING OPERATIONS. CONTRACTOR SHALL REDUCE EFFECTS OF STORM WATER BY USING AND/OR MAINTAINING GRASSED SWALES, INFILTRATION STRUCTURES, OR WATER DIVERSIONS. INSPECT STUCTURAL ELEMENTS DURING WET -SPECIAL PRECAUTIONS SHALL BE TAKEN IN THE USE OF CONSTRUCTION EQUIPMENT TO PREVENT SITUATIONS THAT PROMOTE EROSION. ANNUALLY AND WEATHER AND COMPARE AS-BUILT PLANS (BY -THE CONTRACTOR SHALL PROVIDE ALL EROSION AND SEDIMENT CONTROL MEASURES AS PER THE PLANS. THE CONTRACTOR SHALL BE AT TURNOVER A PROFESSIONAL ENGINEER REPORTING TO RESPONSIBLE FOR MAINTAINING OR MODIFYING CONTROLS DURING CONSTRUCTION BASED ON SITE CONDITIONS TO PREVENT EROSION. -ALL CONTROL MEASURES WILL BE INSPECTED AT LEAST ONCE EACH WEEK AND FOLLOWING ANY STORM EVENT OF 0.5 INCHES OR GREATER. THE DEVELOPER) -ALL MEASURES WILL BE MAINTAINED IN GOOD WORKING ORDER; IF A REPAIR IS NECESSARY, IT WILL INITIATED WITHIN 24 HOURS OF REPORT. -BUILT UP SEDIMENT WILL BE REMOVED FROM SILT FENCE, COMPOST FILTER SOCK, AND ROCK CHECKS WHEN IT HAS REACHED ONE-THIRD THE AS NEEDED* AND MAKE ADJUSTMENTS OR REPLACEMENTS AS PRIOR TO TURNOVER DETERMINED BY PRE-TURNOVER INSPECTION -SILT FENCE AND COMPOST FILTER SOCK WILL BE INSPECTED FOR DEPTH OF SEDIMENT, TEARS, TO SEE IF THE FABRIC IS SECURELY ATTACHED AND TO SEE THAT THE POSTS ARE FIRMLY IN THE GROUND. * AS NEEDED MEANS WHEN SEDIMENT HAS ACCUMULATED TO A MAXIMUM DEPTH OF THREE INCHES FOR THE UNDERGROUND -THE SEDIMENT BASIN WILL BE INSPECTED FOR DEPTH OF SEDIMENT AND BUILT UP SEDIMENT WILL BE REMOVED WHEN IT REACHES 40 PERCENT DETETION SYSTEM AND A MAXIMUM OF ONE FOOT DEPTH FOR THE REMAINDING ITEMS OF THE DESIGN CAPACITY OR AT THE END OF THE JOB. -DIVERSION DIKES WILL BE INSPECTED AND ANY BREACHES WILL BE PROPERLY REPAIRED. -SOIL STOCKPILES SHALL BE STABILIZED OR PROTECTED TO PREVENT SOIL LOSS. -THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CLEANUP OF ANY MUD, DIRT OR DEBRIS DEPOSITED ON ROADS AS A RESULT OF HIS MAINTENANCE TASKS AND SCHEDULE (DURING CONSTRUCTION) OPERATIONS, SOIL SHALL BE REMOVED FROM ROADS AND PAVED SURFACES AT THE END OF EACH DAY, COLLECTED SEDIMENTS HALL BE PLACED IN A STABLE CONDITION ON-SITE OR TAKEN OFF-SITE TO A STABLE LOCATION. -TEMPORARY AND PERMANENT SEEDING AND PLANTING WILL BE INSPECTED FOR BARE SPOTS, WASHOUTS, AND HEALTHY GROWTH. BY CONTRACTOR -A MAINTENANCE INSPECTION REPORT WILL BE MADE AFTER EACH INSPECTION. A COPY OF THE REPORT FORM IS TO BE COMPLETED BY THE INSPECTOR. THE SITE SUPERINTENDENT WILL SELECT INDIVIDUALS WHO WILL BE RESPONSIBLE FOR INSPECTIONS, MAINTENANCE AND REPAIR ACTIVITIES, AND FILLING OUT THE INSPECTION AN MAINTENANCE REPORT. -SOLID, SANITARY AND TOXIC WASTE MUST BE DISPOSED OF IN A PROPER MANNER IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REGULATIONS. IT IS PROHIBITED TO BURN, BURY OR POUR OUT ONTO GROUND OR INTO STORM SEWER ANY SOLVENTS, PAINT, STAINS, **TASKS** JNDERGROUND SEWER CONTROL **SCHEDULE** GASOLINE, DIESEL FUEL, USED MOTOR OIL, HYDRAULIC FLUID, ANTIFREEZE, CEMENT CURING COMPOUNDS AND OTHER SUCH TOXIC OR DETENTION PAVED AREA SYSTEM CASTINGS HAZARDOUS WASTE -WASH OUT OF CEMENT TRUCKS SHOULD OCCUR IN THE DESIGNATED AREA WHERE THE WASHINGS CAN COLLECT AND BE DISPOSED OF INSPECT FOR SEDIMENT ACCUMULATION X X ANNUALLY PROPERLY WHEN THEY HARDEN. -FUEL STORAGE TANKS SHOULD BE LOCATED IN DIKED AREAS AWAY FROM DRAINAGE CHANNELS. THE DIKED AREAS SHOULD HOLD A VOLUME REMOVAL OF SEDIMENT ACCUMULATION X^* AS NEEDED AT LEAST 110% OF THE LARGEST TANK. THE DIKED AREAS ARE NOT NECESSARY IF CONTRACTOR USES SELF-CONTAINED SPILL PROOF TANKS. INSPECT FOR FLOATABLES AND DEBRIS ANNUALLY X X NON-STORMWATER DISCHARGES CLEANING OF FLOATABLES AND DEBRIS ANNUALLY X IT IS EXPECTED THAT THE FOLLOWING STORMWATER DISCHARGES WILL OCCUR FROM THE SITE DURING THE CONSTRUCTION PERIOD: INSPECTION FOR EROSION **ANNUALLY** -WATER FROM WATER LINE FLUSHING. REESTABLISH PERMANENT VEGETATION ON ERODED SLOPES AS NEEDED -PAVEMENT WASH WATERS (WHERE NO SPILLS OR LEAKS OF TOXIC OR HAZARDOUS MATERIALS HAVE OCCURRED). -UNCONTAMINATED GROUNDWATER (FROM DEWATERING EXCAVATION). SEMI-ANNUALLY -ALL NON-STORMWATER DISCHARGES WILL BE DIRECTED TO THE SEDIMENT BASIN PRIOR TO DISCHARGE. CLEAN STREETS -THERE SHALL BE NO SEDIMENT-LADEN DISCHARGE TO SURFACE WATERS RESULTING FROM DEWATERING ACTIVITIES. IT IS RECOMMENDED THAT IF A TRENCH OR GROUND WATER CONTAINS SEDIMENT THAT IS MUST PASS THROUGH A SEDIMENT SETTLING POND OR OTHER EQUALLY AS NEEDED MOWING EFFECTIVE SEDIMENT CONTROL DEVICE PRIOR TO BEING DISCHARGED FROM THE CONSTRUCTION SITE. INSPECT STUCTURAL ELEMENTS DURING WET WEATHER ANNUALLY AND COMPARE AS-BUILT PLANS (BY A PROFESSIONAL **DEWATERING PROCEDURES** ENGINEER REPORTING TO THE DEVELOPER) SHOULD DEWATERING BE REQUIRED, E.G., FROM TRENCHES, ETC., DURING CONSTRUCTION, ALL WATER SHALL BE PUMPED TO THE TEMPORARY SEDIMENT BASINS, IF POSSIBLE, BEFORE BEING RELEASED TO DOWNSTREAM CHANNELS, STORM SEWERS, ETC. IF A TEMPORARY SEDIMENT BASIN IS MAKE ADJUSTMENTS OR REPLACEMENTS AS NOT SHOWN ON THE PLAN, OR NOT ACHIEVABLE FOR DEWATERING, THE WATER SHALL BE PUMPED INTO A SEDIMENT TRAP OR THROUGH SEDIMENT AS NEEDED BAGS ONTO A RELATIVELY FLAT SURFACE AWAY FROM INLET BASINS, STREAMS, ETC. DETERMINED BY PRE-TURNOVER INSPECTION KEEP RECORDS OF ALL INSPECTIONS AND MAINTENANCE ANNUALLY ACTIVITIES AND REPORT TO PROPERTY OWNER MAINTENANCE/INSPECTION PROCEDURES KEEP RECORDS OF ALL COSTS FOR INSPECTIONS, ANNUALLY MAINTENANCE AND REPAIRS. REPORT TO PROPERTY OWNER PROPERTY OWNER REVIEWS COST EFFECTIVENESS OF THE PREVENTATIVE MAINTENANCE PROGRAM AND MAKES NNUALLY THE PROPERTY OWNER OR ITS AUTHORIZED REPRESENTATIVE(S) IS RESPONSIBLE FOR THE INSPECTION OF THE NEWLY INSTALLED STRUCTURES NECESSARY ADJUSTMENTS FOR OUTLET DAMAGE, PROPER FLOW, AND SEDIMENT ACCUMULATIONS. PROPERTY OWNER TO HAVE A PROFESSIONAL ENGINEER MAINTENANCE COSTS, IF INSPECTED BY THE OWNER OR THE OWNER'S REPRESENTATIVE(S), WILL BE PAID BY THE OWNER. CARRY OUT EMERGENCY INSPECTIONS UPON AS NEEDED 3. THE SITE SHALL BE MAINTAINED PER THE POST-CONSTRUCTION MAINTENANCE PLAN FOLLOWING THE SUBMITTAL OF THE (NOT). IDENTIFICATION OF SEVERE PROBLEMS. 4. REGULAR INSPECTIONS, ESPECIALLY FOLLOWING THE MAJOR STORM EVENTS, WILL REQUIRE AN INSPECTION REPORT THAT SHALL BE KEPT BY * AS NEEDED MEANS WHEN SEDIMENT HAS ACCUMULATED TO A MAXIMUM DEPTH OF THREE INCHES FOR THE UNDERGROUND DETETION SYSTEM THE OWNER AND SUBMITTED, IF REQUIRED, TO THE VILLAGE OF SOUTH AMHERST'S ENGINEERING DEPARTMENT. MAINTENANCE TASKS AND SCHEDULE (FOLLOWING CONSTRUCTION) POST-CONSTRUCTION INSPECTION PROCEDURE **BY OWNER**

PROPOSED CORE AND SHELL BUILDING:

Convergent East

2 Equity Way Westlake, OH 44145

JOB NUMBER: 180393.00

DRAWING RELEASE:

No. Date Description
01/04/2019 Permit/Bid Set

SHEET TITLE:

SESC DETAILS

SHEET NUMBER:

CE502

SITE PREPARATION 1. A SUBSOILER, PLOW OR OTHER IMPLEMENT SHALL BE USED TO REDUCE SOIL COMPACTION AND ALLOW MAXIMUM INFILTRATION. (MAXIMIZING INFILTRATION WILL HELP CONTROL BOTH RUNOFF RATE AND WATER QUALITY.) SUBSOILING SHOULD BE DONE WHEN THE SOIL MOISTURE IS LOW ENOUGH TO ALLOW THE SOIL TO CRACK OR FRACTURE, SUBSOILING SHALL NOT BE DONE ON SLIP-PRONE AREAS WHERE SOIL PREPARATION SHOULD BE LIMITED TO WHAT IS NECESSARY FOR ESTABLISHING 2. THE SITE SHALL BE GRADED AS NEEDED TO PERMIT THE USE OF CONVENTIONAL EQUIPMENT FOR SEEDBED PREPARATION AND SEEDING. 3. TOPSOIL SHALL BE APPLIED WHERE NEEDED TO ESTABLISH VEGETATION. SEEDBED PREPARATION 1. LIME - AGRICULTURAL GROUND LIMESTONE SHALL BE APPLIED TO ACID SOIL AS RECOMMENDED BY A SOIL TEST. IN LIEU OF A SOIL TEST, LIME SHALL BE APPLIED AT THE RATE OF 100 POUNDS PER 1,000 SQ FT OR 2 2. FERTILIZER - FERTILIZER SHALL BE APPLIED AS RECOMMENDED BY A SOIL TEST. IN LIEU OF A SOIL TEST, FERTILIZER SHALL BE APPLIED AT A RATE OF 100 POUNDS PER 1000 SQ FT OR 1000 POUNDS PER ACRE OF A 10-10-10 OR 12-12-12 ANALYSES. DORMAN NOTE: OTHE 3 IN 1. MATERIALS - COMPOST USED FOR COMPOST FILTER SOCKS SHALL BE WEED, PATHOGEN AND INSECT FREE AND FREE OF ANY REFUSE, CONTAMINANTS OR OTHER MATERIALS TOXIC TO PLANT GROWTH. THEY SHALL BE DERIVED FROM A WELL-DECOMPOSED SOURCE OF ORGANIC MATTER AND CONSIST OF A PARTICLES RANGING FROM 3/8 IN TO 2 IN. 2. COMPOST FILTER SOCKS SHALL BE 3 OR 5 MIL CONTINUOUS, TUBULAR, HDPE 3/8 IN KNITTED MESH NETTING MATERIAL, FILLED WITH COMPOST PASSING THE ABOVE SPECIFICATIONS FOR COMPOST PRODUCTS. 3. CONTRACTOR SHALL USE COMPOST FILTER SOCK WHEN PAVEMENT SURFACE PROHIBITS THE USE OF SILT FENCE. 4. COMPOST FILTER SOCKS WILL BE PLACED ON A LEVEL LINE ACROSS SLOPES, GENERALLY PARALLEL TO THE BASE OF THE SLOPE OR OTHER AFFECTED AREA. ON SLOPES APPROACHING 2:1, ADDITIONAL SOCKS SHALL BE PROVIDED AT THE TOP AND AS NEEDED 5. COMPOST FILTER SOCKS INTENDED TO BE LEFT AS A PERMANENT FILTER OR PART OF THE NATURAL LANDSCAPE, SHALL BE SEEDED AT THE TIME OF INSTALLATION FRO ESTABLISHMENT OF PERMANENT VEGETATION.

A 10-10-10 OR 12-12-12 ANALYSES. THE LIME AND FERTILIZER SHALL BE WORKE SOIL WITH A DISK HARROW, SPRING—TOOTH OTHER SUITABLE FIELD IMPLEMENT TO A DE INCHES. ON SLOPING LAND THE SOIL SHALL ON THE CONTOUR. NG DATES AND SOIL CONDITIONS SEEDING SHOULD BE DONE MARCH 1 TO MA AUGUST TO SEPTEMBER 30. IF SEEDING OCCOPT THE ABOVE—SPECIFIED DATES, ADDITION, IRRIGATION MAY BE REQUIRED TO ENSURE A 80% GERMINATION. TILLAGE FOR SEEDBED P SHOULD BE DONE WHEN THE SOIL IS DRY E CRUMBLE AND NOT FORM RIBBONS WHEN CONDITIONAL SEEDING. ANT SEEDINGS SEEDINGS SHOULD NOT BE MADE FROM OCTOP THROUGH NOVEMBER 20. DURING THIS PERICARE LIKELY TO GERMINATE BUT PROBABLY ABLE TO SURVIVE THE WITNER. THE FOLLOWING METHODS MAY BE USED FO SEEDING" FROM OCTOBER 1 THROUGH NOVEMBER 20. THE SEEDBED, ADD THE REQUIRED AMOUNT AND FERTILIZER, THEN MULCH AND ANCHONOVEMBER 20, AND BEFORE MARCH 15, BISELECTED SEED MIXTURE. INCREASE THE SED BY 50% FOR THIS TYPE OF SEEDING.	HARROW, OF PTH OF 3 BE WORKED Y 31 OR CURS OUTSID AL MULCH AN MINIMUM ON REPARATION NOUGH TO DWING SECTION OBER 1 DD, THE SEEN WILL NOT BE R "DORMANT BE R "DORMANT BE TS OF LIME R. AFTER ROADCAST THE EEDING RATE WHEN SOIL TO, LIME AND	S EROS ACCC WOOD 3. STRAW MULL LOSS BY W MECH SHAL MULC F ANCH ANCH GENE BY ON MAY AREA SLOP ASPH RECC OF 1 ACR SPEC FIBER A NE WOOD WITH POUR HE IRRIGATION CONDITIONS GERMINATIO	RR — OTHER ACCEPTABLE MULCHES INCLUDE ROLLED SION CONTROL MATTINGS OR BLANKETS APPLIED ORDING TO MANUFACTURER'S RECOMMENDATIONS OR D'CHIPS APPLIED AT 6 TONS PER ACRE. WAND MULCH ANCHORING METHODS CH SHALL BE ANCHORED IMMEDIATELY TO MINIMIZE WIND OR WATER. HANICAL — A DISK, CRIMPER OR SIMILAR TYPE TOOL LL BE SET STRAIGHT TO PUNCH OR ANCHOR THE CH MATERIAL INTO THE SOIL. STRAW MECHANICALLY HORED SHALL NOT BE FINELY CHOPPED, BUT TRALLY BE LEFT LONGER THAN 6 INCHES. CH NETTING — NETTING SHALL BE USED ACCORDING THE MANUFACTURER'S RECOMMENDATIONS. NETTING BE NECESSARY TO HOLD MULCH IN PLACE IN AS OF CONCENTRATED RUNOFF AND ON CRITICAL	NOVEN NOTE: O GEN 1.
FERTILIZE, APPLY THE SELECTED SEED MIX AND ANCHOR. INCREASE THE SEEDING RAT FOR THIS TYPE OF SEEDING.		IRRIGATION	RATES SHALL BE MONITORED TO PREVENT EROSION GE TO SEEDED AREAS FROM EXCESSIVE RUNOFF.	2.
NEXT SEEDING				ı
NENT SEEDING	CEED	INIC DATE		3.
CEED MIN		OING RATE	NOTES:	J.
SEED MIX	LB/AC	LB/1000 FT ² NERAL USE		
CREEPING RED FESCUE	20-40	.5-1	FOR CLOSE MOWING & FOR WATERWAYS	
			WITH <2.0 FT/SEC VELOCITY	
DOMESTIC RYGRASS	10-20	.255	WIIII \2.0 I I/SEC VELOCII I	MUL
KENTUCKY BLUEGRASS	10-20	.255		
TALL FESCUE	40-50	1-1.25		1.
TURF-TYPE (DWARF) FESCUE	90	2.25		
, ,		KS OR CUT SLO	PES	
			FES	
TALL FESCUE	40-50	1-1.25	DO NOT CEED A LEED TO	•
CROWN VETCH	10-20	.255	DO NOT SEED LATER THAN AUGUST	
TALL FESCUE	20-30	.575		2.
FLAT PEA	20-25	.575	DO NOT SEED LATER THAN AUGUST	
TALL FESCUE	20-30	.575		
		CHES AND SWA	I FS	
TALL FESCUE	40-50	1-1.25	LLG	
TURF TYPE (DWARF) FESCUE				
,	90	2.25		
KENTUCKY BLUEGRASS	5	0.1		
		LAWNS		
KENTUCKY BLUEGRASS	100-120	2		
PERENNIAL RYEGRASS		2		
KENTUCKY BLUEGRASS	100-120	2	EOD CHADED ADEAC	
CREEPING RED FESCUE		1.5	FOR SHADED AREAS	
HER APPROVED SEED SPECIES MAY BE SUBSTITU	ITED			
TIEK APPROVED SEED SPECIES MAY BE SUBSTITU	IEU			
CDECIEICATIO	NIC EC	D DEDA4	NIENIT CEEDING	
SPECIFICATIO	IND LC	'N LEKWI	ANENT SEEDING	
				
		- 2 IN X 2 IN WOO	DEN STAKE	
1		Z 114 A Z 114 WUC	JULI STANL	
<u> </u>			FLOW	
IN-4 IN		COMI	POST FILTER SOCK	
		COMI	1	
		\//\/\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\		

SECTION

6. COMPOST FILTER SOCKS ARE NOT TO BE USED IN CONCENTRATED FLOW SITUATIONS OR IN RUNOFF CHANNELS.

AND NOT OBSTRUCT SEEDINGS, OR REMOVED AND DISPOSED OF OFF-SITE.

7. ROUTINELY INSPECT COMPOST FILTER SOCKS AFTER EACH SIGNIFICANT RAIN, MAINTAINING COMPOST FILTER SOCKS IN A FUNCTIONAL

8. REMOVE SEDIMENTS COLLECTED AT THE BASE OF THE COMPOST FILTER SOCKS WHEN THEY REACH 1/3 OF THE EXPOSED HEIGHT OF

10. REMOVAL - COMPOST FILTER SOCKS WILL BE DISPERSED ON SITE WHEN NO LONGER REQUIRED IN SUCH A WAY AS TO FACILITATE

COMPOST FILTER SOCK

9. WHERE THE COMPOST FILTER SOCK DETERIORATES OR FAILS, IT WILL BE REPAIRED OR REPLACED WITH A MORE EFFECTIVE

APPLY SEED UNIFORMLY WITH A CYCLONE SEEDER, DRILL

INCLUDE SEED AND FERTILIZER) ON A FIRM MOIST

WHERE FEASIBLE, EXCEPT WHEN A CULTIPACKER TYPE

SEEDER IS USED, THE SEEDBED SHOULD BE FIRMED

ROLLER OR LIGHT DRAG. ON SLOPING LAND, SEEDING

OPERATIONS SHOULD BE ON THE CONTOUR WHERE

1. MULCH MATERIAL SHALL BE APPLIED IMMEDIATELY AFTER SEEDING. DORMANT SEEDING SHALL BE MULCHED. 100% OF THE GROUND SURFACE SHALL BE COVERED WITH AN

STRAW — IF STRAW IS USED IT SHALL BE UNROTTED

BY HAND OR MECHANICALLY APPLIED SO THE SOIL SURFACE IS COVERED. FOR UNIFORM DISTRIBUTION OF

TWO 45 LB BALES OF STRAW IN EACH SECTION. HYDROSEEDERS — IF WOOD CELLULOSE FIBER IS USED,

HAND-SPREAD MULCH, DIVIDE AREA INTO

SMALL-GRAIN STRAW APPLIED AT THE RATE OF 2 TONS

PER ACRE OR 90 POUNDS (TWO TO THREE BALES) PER

1000 SQ FT, THE MULCH SHALL BE SPREAD UNIFORMLY

APPROXIMATELY 1000 SQ FT SECTIONS AND SPREAD

IT SHALL BE APPLIED AT 2000 LB/AC OR 46 LB/1000

FOLLOWING SEEDING OPERATIONS WITH A CULTIPACKER,

SEEDBED.

APPROVED MATERIAL.

CULTIPACKER SEEDER, OR HYDRO-SEEDER (SLURRY MAY

TEMPORARY SEEDING SPECIES S	SELECTION]
SEEDING DATES		SPECIES	LB./1,000 FT. ²	LB/PER AC.	
MARCH 1 TO AUGUST 15		OATS	3	128 (4 BUSHEL)	1
		TALL FESCUE	1	40	
		ANNUAL RYEGRASS	1	40	
		PERENNIAL RYEGRASS	1	40	
		TALL FESCUE	1	40	
		ANNUAL RYEGRASS	1	40	14 FT MINIMUM
		ANNUAL RYEGRASS	1.25	55	AND NOT LESS
		PERENNIAL RYEGRASS	3.25	142	THAN WIDTH OF INGRESS OR EGRES
		CREEPING RED FESCUE	0.4	17	
		KENTUCK BLUEGRASS	0.4	17	∐ ↓
		OATS	3	128 (3 BUSHEL)	
		TALL FESCUE	1	40	
		ANNUAL RYEGRASS	1	40	
AUGUST 16 TO NOVEMBER 1		RYE	3	112 (2 BUSHEL)	
		TALL FESCUE	1	40	
		ANNUAL RYEGRASS	1	40	
		WHEAT	3	120 (2 BUSHEL)	
		TALL FESCUE	1	40	
		ANNUAL RYEGRASS	1	40	
		PERENNIAL RYEGRASS	1	40	
		TALL FESCUE	1	40	
		ANNUAL RYEGRASS	1	40	
		ANNUAL RYEGRASS	1.25	40	
		PERENNIAL RYEGRASS	3.25	40	-0
		CREEPING RED FESCUE	0.4	40	
		KENTUCK BLUEGRASS	0.4		
NOVEMBER 1 TO FEBRUARY 29		USE MULCH ONLY OR D	ORMANT SEEDING		_
NOTE: OTHER APPROVED SEED SPECIES MAY	Y BE SUBSTITUTED				
GENERAL NOTES:			NDMENTS — TEMPORARY : TABLISH ADEQUATE STANI		
1. STRUCTURAL EROSION AND SED		VEGETATIO	N, WHICH MAY REQUIRE	THE USE OF	
PRACTICES SUCH AS DIVERSION TRAPS SHALL BE INSTALLED AN			NDMENTS, BASE RATES FO R SHALL BE USED.	OR LIME AND	
TEMPORARY SEEDING PRIOR TO	GRADING THE				NOTES:
REST OF THE CONSTRUCTION-S	SITE.		METHOD — SEED SHALL B Y WITH A CYCLONE SPREA		1. STONE SIZE - OF
2. TEMPORARY SEED SHALL BE AF		CULTIPACK	KER SEEDER, OR HYDROSE	EEDER. WHEN	2. LENGTH— THE CO
CONSTRUCTION OPERATIONS ON NOT BE GRADED OR REWORKED			SEED THAT HAS BEEN B COVERED BY RAKING OR		THAN 70 FT (EXC
GREATER, THESE IDLE AREAS S	SHALL BE SEEDED	THEN LIGH	HTLY TAMPED INTO PLACE	USING A	3. THICKNESS — THE
WITHIN 7 DAYS AFTER GRADING	2.	USED, THE	R CULTIPACKER. IF HYDRO E SEED AND FERTILIZER V	VILL BE MIXED	FOR HEAVY DUTY
 THE SEEDBED SHOULD BE PULY TO ENSURE THE SUCCESS OF E 		ON-SITE A	AND THE SEEDING SHALL LY AND WITHOUT INTERRU	BE DONE	4. WIDTH — THE EN
VEGETATION, TEMPORARY SEEDI	NG SHOULD NOT	IMMEDIATE	LI AND WITHOUT INTERRU	JI IION,	OR EGRESS OCCU
BE POSTPONED IF IDEAL SEEDB IS NOT POSSIBLE.	BED PREPARATION				5. GEOTEXTILE - A
					STRONG ROT-PRO
MULCHING TEMPORARY SEEDING:			JLCH SHALL BE ANCHORE		
1. APPLICATIONS OF TEMPORARY S	SEEDING SHALL		ZE LOSS BY WIND OR WA G METHODS:	IER.	N
INCLUDE MULCH, WHICH SHALL	BE APPLIED			00 0040 45	<u> </u>
DURING OR IMMEDIATELY AFTER SEEDINGS MADE DURING OPTIMU	JM SEEDING DATES	TYPE TO	NICAL — A DISK, CRIMPER OOL SHALL BE SET STRAI		<u> </u>
ON FAVORABLE, VERY FLAT SOL	I CONDITIONS MAY		CHOR THE MULCH MATERIA		l I

ON FAVORABLE, VERY FLAT SOIL CONDITIONS MAY

UNROTTED SMALL-GRAIN STRAW APPLIED AT A

RATE OF 2 TONES PER ACRE OR 90 LBS/1000

HYDROSEEDERS — IF WOOD CELLULOSE FIBER IS

USED, IT SHALL BE USED AT 2000 LBS/AC OR

INCLUDE MULCH MATTINGS APPLIED ACCORDING

COMPOST FILTER SOCK

SEEDING TO ALL STOCKPILES WHICH WILL REMAIN IN PLACE 20 DAYS OR MORE.

WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.

4. STOCKPILE PERIMETER CONTROLS CAN BE REMOVED ONCE ALL THE MATERIAL FROM THE STOCKPILE HAS BEEN USED.

5. STOCKPILES SHALL BE INSPECTED DAILY AND NOTED DEFICIENCIES SHALL BE PROMPTLY ADDRESSED.

WHEN TEMPORARY REMOVAL OF A PERIMETER BMP IS NECESSARY TO ACCESS A STOCKPILE, ENSURE BMPS ARE REINSTALLED IN

. WHEN THE STOCKPILE IS NO LONGER NEEDED, PROPERLY DISPOSE OF EXCESS MATERIALS AND REVEGETATE OR OTHERWISE STABILIZE

STOCKPILE AREA

•••••••

MAINTENANCE NOTES:

PLAN VIEW

ACCORDANCE WITH THEIR RESPECTIVE DESIGN DETAIL SECTION.

THE GROUND SURFACE WHERE THE STOCKPILE WAS LOCATED.

TO MANUFACTURER'S RECOMMENDATIONS OR

NOT NEED MULCH TO ACHIEVE ADEQUATE

STRAW - IF STRAW IS USED, IT SHALL BE

OTHER - OTHER ACCEPTABLE MULCHES

WOOD CHIPS APPLIED AT 6 TON/AC.

MATERIALS:

SQ FT (2-3 BALES).

46 LB/ 1000 SQ FT.

OR ANCHOR THE MULCH MATERIAL INTO THE

SOIL. STRAW MECHANICALLY ANCHORED SHALL

NOT BE FINELY CHOPPED BUT LEFT TO A

LENGTH OF APPROXIMATELY 6 INCHES.

MULCH NETTING - NETTING SHALL BE USED

NECESSARY TO HOLD MULCH IN PLACE IN

• SYNTHETIC BINDERS - SYNTHETIC BINDERS

WOOD—CELLULOSE FIBER — WOOD—CELLULOSE

FIBER BINDER SHALL BE APPLIED AT A NET

DRY WT OF 750 LB/AC. THE WOOD-CELLULOSE

35 FT. MAX.

FIBER SHALL BE MIXED WITH WATER AND THE

MIXTURE SHALL CONTAIN A MAXIMUM OF 50

AREAS OF CONCENTRATED RUNOFF AND ON

SUCH AS ACRYLIC DLR (AGRI-TAC), DCA-70,

PETROSET, TERRA TRACK OR EQUIVALENT MAY BE USED AT RATES RECOMMENDED BY THE

ACCORDING TO THE MANUFACTURERS


RECOMMENDATIONS. NETTING MAY BE

CRITICAL SLOPES.

MANUFACTURER.


SPECIFICATIONS FOR TEMPORARY SEEDING

COMPOST FILTER SOCK -



---- 70 FT (OR 30 FT FOR ACCESS TO INDIVIDUAL HOUSE LOT) ---

- RIGHT OF WAY DIVERSION



GEOTEXTILE FILTER BAG

Convergent East 2 Equity Way Westlake, OH 44145

PROPOSED CORE AND

SHELL BUILDING:

JOB NUMBER: **180393.00**

DRAWING RELEASE: No. Date 01/04/2019 Permit/Bid Set

SESC DETAILS


SHEET NUMBER:


SHEET TITLE:


10/24/2018


CONDITION AT ALL TIMES.


THE PRACTICE.












13

DRWN BY:



2 Equity Way Westlake, OH 44145

PROPOSED CORE AND

SHELL BUILDING:


Convergent East

JOB NUMBER: **180393.00**


DRAWING RELEASE: No. Date Description 01/04/2019 Permit/Bid Set SHEET TITLE:


DETAILS


SHEET NUMBER:





10/24/2018

















PVC DETAILS







PROPOSED CORE AND SHELL BUILDING:


Convergent East


2 Equity Way Westlake, OH 44145

<u> </u>		
DF	KAVVINC	RELEASE:
No.	Date	Description
	01/04/2019	Permit/Bid Set

CLEVELAND WATER DETAILS

SHEET NUMBER:





REFLECTIVE GOLD OR YELLOW COLORS.









EQUITY TRUST CONVERGENT EAST

WESTLAKE - OH

SC-740 STORMTECH CHAMBER SPECIFICATIONS

- 1. CHAMBERS SHALL BE STORMTECH SC-740. CHAMBERS SHALL BE ARCH-SHAPED AND SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE
- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS'
- CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO INTERNAL SUPPORTS THAT WOULD IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION. THE STRUCTURAL DESIGN OF THE CHAMBERS, THE STRUCTURAL BACKFILL, AND THE INSTALLATION REQUIREMENTS SHALL ENSURE THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1)
- ONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE AASHTO DESIGN TRUCK WITH CONSIDERATION FOR IMPACT AND MULTIPLE VEHICLE PRESENCES
- 6. CHAMBERS SHALL BE DESIGNED, TESTED AND ALLOWABLE LOAD CONFIGURATIONS DETERMINED IN ACCORDANCE WITH ASTM F2787, "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS"
 LOAD CONFIGURATIONS SHALL INCLUDE: 1) INSTANTANEOUS (<1 MIN) AASHTO DESIGN TRUCK LIVE LOAD ON MINIMUM COVER 2) MAXIMUM PERMANENT (75-YR) COVER LOAD AND 3) ALLOWABLE COVER WITH PARKED (1-WEEK) AASHTO DESIGN TRUCK.
- REQUIREMENTS FOR HANDLING AND INSTALLATION: TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING
- . TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS
- TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 550 LBS/IN/IN. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM
- ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED, UPON REQUEST BY THE SITE DESIGN ENGINEER OR OWNER, THE CHAMBER MANUFACTURER SHALL SUBMIT A STRUCTURAL EVALUATION FOR APPROVAL BEFORE
- DELIVERING CHAMBERS TO THE PROJECT SITE AS FOLLOWS: THE STRUCTURAL EVALUATION SHALL BE SEALED BY A REGISTERED PROFESSIONAL ENGINEER. THE STRUCTURAL EVALUATION SHALL DEMONSTRATE THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR
- DEAD LOAD AND 1.75 FOR LIVE LOAD, THE MINIMUM REQUIRED BY ASTM F2787 AND BY SECTIONS 3 AND 12.12 OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS FOR THERMOPLASTIC PIPE. THE TEST DERIVED CREEP MODULUS AS SPECIFIED IN ASTM F2418 SHALL BE USED FOR PERMANENT DEAD LOAD DESIGN
- EXCEPT THAT IT SHALL BE THE 75-YEAR MODULUS USED FOR DESIGN. 9. CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.

ADVANCED DRAINAGE SYSTEMS, INC.





IMPORTANT - NOTES FOR THE BIDDING AND INSTALLATION OF THE SC-740 SYSTEM


- STORMTECH SC-740 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLERS. 2. STORMTECH SC-740 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- 3. CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR AN EXCAVATOR SITUATED OVER THE CHAMBERS. STORMTECH RECOMMENDS 3 BACKFILL METHODS:
- STONESHOOTER LOCATED OFF THE CHAMBER BED. BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE.
 BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
- THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS.
- 5. JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE.

NOTES FOR CONSTRUCTION EQUIPMENT

- 6. MAINTAIN MINIMUM 6" (150 mm) SPACING BETWEEN THE CHAMBER ROWS.
- EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE 3/4-2" (20-50 mm). 8. THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIALS BEARING CAPACITIES TO THE SITE DESIGN
- 9. ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.
- STORMTECH SC-740 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE". . THE USE OF CONSTRUCTION EQUIPMENT OVER SC-740 CHAMBERS IS LIMITED:
- NO EQUIPMENT IS ALLOWED ON BARE CHAMBERS. NO RUBBER TIRED LOADERS, DUMP TRUCKS, OR EXCAVATORS ARE ALLOWED UNTIL PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE. WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE". WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- 3. FULL 36" (900 mm) OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK TRAVEL OR DUMPING. USE OF A DOZER TO PUSH EMBEDMENT STONE BETWEEN THE ROWS OF CHAMBERS MAY CAUSE DAMAGE TO THE CHAMBERS AND IS NOT AN
- CONTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT.







PROPOSED CORE AND SHELL BUILDING:


Convergent East


JOB NUMBER: **180393.00**





STORM SYSTEM **DETAILS**

SHEET NUMBER:









PROPOSED CORE AND SHELL BUILDING:

Convergent East

2 Equity Way Westlake, OH 44145


JOB NUMBER: **180393.00**


DRAWING RELEASE:

No. Date Description
O1/04/2019 Permit/Bid Set

STORM SYSTEM DETAILS

SHEET NUMBER:






PROPOSED CORE AND SHELL BUILDING: Convergent East 2 Equity Way Westlake, OH 44145 JOB NUMBER: **180393.00** DRAWING RELEASE: Description
Permit/Bid Set SHEET TITLE: **DETAILS**

NOTE:

is not responsible for the structural design or engineering for the proposed structure.


SHEET NUMBER:





NOTE:


is not responsible for the structural design or engineering for the proposed structure.

SHEET NUMBER:









PROPOSED CORE AND SHELL BUILDING: Convergent East 2 Equity Way Westlake, OH 44145 JOB NUMBER: **180393.00** DRAWING RELEASE: 01/04/2019 Permit/Bid Set SHEET TITLE: **DETAILS** SHEET NUMBER:

CS511

NOTE:

is not responsible for the structural design or engineering for the proposed structure.